

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015091.00

PROJECTS

-----

BH-1509(100)X

COUNTY : SAGadahoc

CONTRACT ID : 015091.00

BRIDGE REMOVAL

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	06/01/10	\$ 0.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015091.00

PROJECT(S): BH-1509(100)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.11 CLEARING	1.500 AC				
0020	202.19 REMOVING EXISTING BRIDGE LS	LUMP	LUMP			
0030	203.20 COMMON EXCAVATION	37700.000 CY				
0040	203.24 COMMON BORROW	10.000 CY				
0050	203.25 GRANULAR BORROW	10.000 CY				
0060	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	10.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	4950.000 CY				
0080	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	8.000 T				
0090	403.210 HOT MIX ASPHALT 9.5 MM HMA	630.000 T				
0100	403.213 HOT MIX ASPHALT 12.5 MM BASE	640.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015091.00

PROJECT(S): BH-1509(100)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	409.15 BITUMINOUS TACK COAT - APPLIED	150.000 G				
0120	411.09 UNTREATED AGGREGATE SURFACE COURSE	40.000 CY				
0130	603.16 15 INCH CULVERT PIPE OPTION I	126.000 LF				
0140	603.1752 18 INCH REINFORCED CONCRETE PIPE CLASS IV	92.000 LF				
0150	603.209 30 INCH CULVERT PIPE OPTION III	84.000 LF				
0160	606.1722 BRIDGE TRANSITION - TYPE 2	2.000 EA				
0170	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	437.500 LF				
0180	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	25.000 LF				
0190	606.25 TERMINAL CONNECTOR	2.000 EA				
0200	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA				
0210	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	4.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015091.00

PROJECT(S): BH-1509(100)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	606.47 SINGLE WOOD POST	1.000 EA				
0230	606.79 GUARDRAIL 350 FLARED TERMINAL	1.000 EA				
0240	610.08 PLAIN RIPRAP	30.000 CY				
0250	610.18 STONE DITCH PROTECTION	10.000 CY				
0260	613.319 EROSION CONTROL BLANKET	20.000 SY				
0270	615.07 LOAM	480.000 CY				
0280	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	88.000 UN				
0290	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	6.000 UN				
0300	619.1201 MULCH - PLAN QUANTITY	94.000 UN				
0310	619.1401 EROSION CONTROL MIX	960.000 CY				
0320	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	6900.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015091.00

PROJECT(S): BH-1509(100)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0340	629.05 HAND LABOR, STRAIGHT TIME	80.000 HR				
0350	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0360	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				
0370	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR )	20.000 HR				
0380	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0390	637.071 DUST CONTROL	LUMP	LUMP			
0400	639.18 FIELD OFFICE TYPE A	1.000 EA				
0410	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP			
0420	648.5205 RECONSTRUCT GRADE CROSSING	LUMP	LUMP			
0430	648.5206 HIGHWAY GRADE CROSSING SIGNAL SYSTEM	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015091.00

PROJECT(S): BH-1509(100)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	652.31 TYPE I BARRICADE	10.000 EA				
0450	652.312 TYPE III BARRICADE	8.000 EA				
0460	652.33 DRUM	150.000 EA				
0470	652.34 CONE	350.000 EA				
0480	652.35 CONSTRUCTION SIGNS	400.000 SF				
0490	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0500	652.38 FLAGGER	240.000 HR				
0510	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0520	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

