

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015093.00

PROJECTS

015093.00

COUNTY : PENOBSCOT

CONTRACT ID : 015093.00

SCOPE OF WORK: CREAMERY BRIDGE REPLACEMENT AND OTHER INCIDENTAL WORK. LOCATION: IN PENOBSCOT COUNTY, PROJECT IS LOCATED OVER ROLLINS BROOK ON ROUTE 11 APPROXIMATELY 1.8 MILES NORTH OF THE TOWN LINE.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	11/01/09	\$ 575.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015093.00

PROJECT(S): 015093.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	1850.000 CY				
0030	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	46.000 CY				
0040	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1600.000 CY				
0050	403.207 HOT MIX ASPHALT 19.0 MM HMA	120.000 T				
0060	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	320.000 T				
0070	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	4.000 T				
0080	409.15 BITUMINOUS TACK COAT - APPLIED	28.000 G				
0090	502.111 STRUCTURAL CONCRETE FOOTINGS	LUMP	LUMP			
0100	508.13 MEMBRANE WATERPROOFING	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015093.00

PROJECT(S): 015093.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	511.07 COFFERDAM: ABUTMENT NO. 1	LUMP	LUMP			
0120	511.07 COFFERDAM: ABUTMENT NO. 2	LUMP	LUMP			
0130	512.081 FRENCH DRAINS	LUMP	LUMP			
0140	513.22 CRUSHED STONE SLOPE PROTECTION	270.000 SY				
0150	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0160	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0170	526.30 TEMPORARY CONCRETE BARRIER - TYPE 1	60.000 LF				
0180	527.303 ENERGY ABSORBING SYSTEM (ET-PLUS)	1.000 EA				
0190	534.70 PRECAST STRUCTURAL CONCRETE ARCH	LUMP	LUMP			
0200	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	350.000 LF				
0210	606.2301 GR TY 3C - DOUBLE RAIL	75.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015093.00

PROJECT(S): 015093.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0230	606.79 GUARDRAIL 350 FLARED TERMINAL	3.000 EA				
0240	610.08 PLAIN RIPRAP	225.000 CY				
0250	615.07 LOAM	45.000 CY				
0260	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	4.000 UN				
0270	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	3.500 UN				
0280	619.12 MULCH	7.500 UN				
0290	619.1401 EROSION CONTROL MIX	90.000 CY				
0300	620.58 NON WOVEN GEOTEXTILE	700.000 SY				
0310	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	1450.000 LF				
0320	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	50.000 SF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015093.00

PROJECT(S): 015093.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	627.77 REMOVING PAVEMENT MARKINGS	50.000 SF				
0340	629.05 HAND LABOR, STRAIGHT TIME	25.000 HR				
0350	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	15.000 HR				
0360	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	15.000 HR				
0370	635.14 PREFABRICATED CONCRETE MODULAR GRAVITY WALL	212.000 SF				
0380	639.19 FIELD OFFICE TYPE B	1.000 EA				
0390	643.60 FLASHING BEACON AT: SCHOOL, ROAD AND MAIN ROAD	LUMP	LUMP			
0400	645.103 DEMOUNT GUIDE SIGN	1.000 EA				
0410	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	5.000 EA				
0420	645.113 REINSTALL GUIDE SIGN	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015093.00

PROJECT(S): 015093.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	5.000 EA				
0440	652.35 CONSTRUCTION SIGNS	600.000 SF				
0450	652.38 FLAGGER	150.000 HR				
0460	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0470	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0480	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

