

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015097.00

PROJECTS

BR-1509(700)X

COUNTY : AROOSTOOK

CONTRACT ID : 015097.00

IRON BR. REPL. AND OTHER INCID. WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	11/15/10	\$ 900.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015097.00

PROJECT(S): BR-1509(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.10 REMOVING EXISTING SUPERSTRUCTURE (PROPERTY OF CONTRACTOR)	LUMP	LUMP			
0020	202.17 REMOVING EXISTING STRUCTURAL CONCRETE	LUMP	LUMP			
0030	203.20 COMMON EXCAVATION	1410.000 CY				
0040	203.25 GRANULAR BORROW	390.000 CY				
0050	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	890.000 CY				
0060	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	55.000 CY				
0070	304.13 DENSE GRADED CRUSHED AGGREGATE SUBBASE	1650.000 CY				
0080	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	90.000 T				
0090	403.210 HOT MIX ASPHALT 9.5 MM	480.000 T				
0100	409.15 BITUMINOUS TACK COAT - APPLIED	100.000 G				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015097.00

PROJECT(S): BR-1509(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0120	502.239 STRUCTURAL CONCRETE PIERS	LUMP	LUMP			
0130	502.2611 STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON CONCRETE BRIDGE	320.000 CY				
0140	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0150	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			
0160	502.56 CONCRETE FILL	55.000 CY				
0170	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	179900.000 LB				
0180	503.13 REINFORCING STEEL, PLACING	179900.000 LB				
0190	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP	LUMP			
0200	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0210	511.07 COFFERDAM: ABUTMENT NO.1	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015097.00

PROJECT(S): BR-1509(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	511.07 COFFERDAM: ABUTMENT NO.2	LUMP	LUMP			
0230	511.07 COFFERDAM: PIER	LUMP	LUMP			
0240	512.081 FRENCH DRAINS	LUMP	LUMP			
0250	514.06 CURING BOX FOR CONCRETE CYLINDERS	3.000 EA				
0260	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0270	523.52 BEARING INSTALLATION	24.000 EA				
0280	523.5401 LAMINATED ELASTOMERIC BEARINGS, FIXED	12.000 EA				
0290	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	12.000 EA				
0300	526.30 TEMPORARY CONCRETE BARRIER - TYPE 1	80.000 LF				
0310	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				
0320	527.305 QUADGUARD CRASH CUSHION	1.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015097.00

PROJECT(S): BR-1509(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT		
			DOLLARS	CTS	DOLLARS	CTS	
0330	535.61 PRESTRESSED STRUCTURAL CONCRETE I-GIRDERS	LUMP	LUMP				
0340	603.179 18 INCH CULVERT PIPE OPTION III	202.000 LF					
0350	603.199 24 INCH CULVERT PIPE OPTION III	90.000 LF					
0360	604.164 REBUILDING CATCH BASIN	1.000 EA					
0370	604.247 CATCH BASIN TYPE F5-C	4.000 EA					
0380	604.252 CATCH BASIN TYPE A5-C	5.000 EA					
0390	605.13 18 INCH UNDERDRAIN TYPE C	312.000 LF					
0400	606.1721 BRIDGE TRANSITION - TYPE 1	3.000 EA					
0410	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	125.000 LF					
0420	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	25.000 LF					
0430	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	3.000 EA					

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015097.00

PROJECT(S): BR-1509(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	10.000 EA				
0450	606.79 GUARDRAIL 350 FLARED TERMINAL	2.000 EA				
0460	607.16 CHAIN LINK FENCE - 4 FOOT	16.000 LF				
0470	609.31 CURB TYPE 3	410.000 LF				
0480	610.08 PLAIN RIPRAP	465.000 CY				
0490	613.319 EROSION CONTROL BLANKET	42.000 SY				
0500	615.07 LOAM	55.000 CY				
0510	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	11.000 UN				
0520	619.12 MULCH	11.000 UN				
0530	619.1401 EROSION CONTROL MIX	20.000 CY				
0540	620.58 EROSION CONTROL GEOTEXTILE	780.000 SY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015097.00

PROJECT(S): BR-1509(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	626.22 NON-METALLIC CONDUIT	60.000 LF				
0560	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	2950.000 LF				
0570	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR				
0580	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	24.000 HR				
0590	631.14 GRADER (INCLUDING OPERATOR)	12.000 HR				
0600	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	12.000 HR				
0610	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	24.000 HR				
0620	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	24.000 HR				
0630	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	12.000 HR				
0640	631.22 FRONT END LOADER (INCLUDING OPERATOR)	12.000 HR				
0650	634.16 HIGHWAY LIGHTING	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015097.00

PROJECT(S): BR-1509(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0660	634.21 CONVENTIONAL LIGHT STANDARD	1.000 EA				
0670	635.14 PREFABRICATED CONCRETE MODULAR GRAVITY WALL	1125.000 SF				
0680	637.071 DUST CONTROL	LUMP	LUMP			
0690	638.01 EMBEDDED WORK IN STRUCTURE	LUMP	LUMP			
0700	639.18 FIELD OFFICE TYPE A	1.000 EA				
0710	652.312 TYPE III BARRICADE	14.000 EA				
0720	652.33 DRUM	30.000 EA				
0730	652.34 CONE	30.000 EA				
0740	652.35 CONSTRUCTION SIGNS	330.000 SF				
0750	652.38 FLAGGER	1250.000 HR				
0760	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015097.00

PROJECT(S): BR-1509(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0770	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0780	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					