

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015100.00

PROJECTS

015100.00

COUNTY : ANDROSCOGGIN

CONTRACT ID : 015100.00

SCOPE OF WORK: DURGIN BRIDGE REPLACEMENT AND OTHER INCIDENTAL WORK. IN ANDROSCOGGIN COUNTY, PROJECT IS LOCATED ON KING ROAD OVER SABATTUS STREAM APPROXIMATELY 0.1 MILE EAST OF LITTLEFIELD ROAD.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	05/15/10	\$ 575.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015100.00

PROJECT(S): 015100.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	600.000 CY				
0030	203.24 COMMON BORROW	570.000 CY				
0040	203.25 GRANULAR BORROW	270.000 CY				
0050	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	310.000 CY				
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1050.000 CY				
0070	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	140.000 T				
0080	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	13.000 T				
0090	403.213 HOT MIX ASPHALT 12.5 MM BASE	95.000 T				
0100	501.231 DYNAMIC LOADING TEST	2.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015100.00

PROJECT(S): 015100.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	501.48 STEEL H-BEAM PILES 74 LBS/FT, DELIVERED	270.000 LF				
0120	501.481 STEEL H-BEAM PILES 74 LBS/FT, IN PLACE	220.000 LF				
0130	501.90 PILE TIPS	6.000 EA				
0140	501.91 PILE SPLICES	3.000 EA				
0150	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
0160	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0170	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP	LUMP			
0180	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	9000.000 LB				
0190	503.13 REINFORCING STEEL, PLACING	9000.000 LB				
0200	503.14 EPOXY COATED REINFORCING STEEL, FABRICATED AND DELIVERED	29300.000 LB				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015100.00

PROJECT(S): 015100.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	503.15 EPOXY COATED REINFORCING STEEL PLACING	29300.000 LB				
0220	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			
0230	505.08 SHEAR CONNECTORS	LUMP	LUMP			
0240	507.0811 STEEL BRIDGE RAILING, 2 BAR	LUMP	LUMP			
0250	511.07 COFFERDAM: ABUTMENT #1	LUMP	LUMP			
0260	511.07 COFFERDAM: ABUTMENT #2	LUMP	LUMP			
0270	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0280	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0290	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0300	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				
0310	603.17 18 INCH CULVERT PIPE OPTION I	20.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015100.00

PROJECT(S): 015100.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	603.179 18 INCH CULVERT PIPE OPTION III	80.000 LF				
0330	603.19 24 INCH CULVERT PIPE OPTION I	28.000 LF				
0340	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				
0350	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	112.500 LF				
0360	606.78 LOW VOLUME GUARDRAIL ENDS - TYPE 3	4.000 EA				
0370	610.08 PLAIN RIPRAP	630.000 CY				
0380	610.18 STONE DITCH PROTECTION	75.000 CY				
0390	613.319 EROSION CONTROL BLANKET	125.000 SY				
0400	615.0701 LOAM - PLAN QUANTITY	50.000 CY				
0410	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	9.000 UN				
0420	619.1201 MULCH - PLAN QUANTITY	9.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015100.00

PROJECT(S): 015100.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	620.58 NON WOVEN GEOTEXTILE	750.000 SY				
0440	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	1575.000 LF				
0450	637.071 DUST CONTROL	LUMP	LUMP			
0460	639.19 FIELD OFFICE TYPE B	1.000 EA				
0470	652.312 TYPE III BARRICADE	4.000 EA				
0480	652.33 DRUM	10.000 EA				
0490	652.34 CONE	10.000 EA				
0500	652.35 CONSTRUCTION SIGNS	600.000 SF				
0510	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0520	652.38 FLAGGER	40.000 HR				
0530	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015100.00

PROJECT(S): 015100.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

SCHEDULE OF ITEMS

DATE:
REVISED:

CONTRACT ID: 015100.00

PROJECT(S): 015100.00

LIST ITEMS ON THIS PAGE BY AMENDMENT

CONTRACTOR :

Table with 7 columns: LINE NO, ITEM DESCRIPTION, APPROX. QUANTITY AND UNITS, UNIT PRICE (DOLLARS, CTS), BID AMOUNT (DOLLARS, CTS). Includes a row for TOTAL BID.

SPECIAL PROVISIONS ATTACHED