

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015107.00

PROJECTS

-----

BR-1510(700)X

COUNTY : CUMBERLAND

CONTRACT ID : 015107.00

STANDISH, BRIDGE REPLACEMENT. WORK INCLUDES SEBAGO LAKE  
ROAD CROSSING BRIDGE REPLACEMENT AND OTHER INCIDENTAL WORK.

-----			
SITE	CONTRACT TIME	LIQUIDATED DAMAGES	
-----			
CONTRACT	11/15/11	\$	0.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015107.00

PROJECT(S): BR-1510(700)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.11 CLEARING	1.000 AC				
0020	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0030	203.20 COMMON EXCAVATION	15205.000 CY				
0040	203.21 ROCK EXCAVATION	50.000 CY				
0050	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	7575.000 CY				
0060	403.207 HOT MIX ASPHALT 19.0 MM HMA	1465.000 T				
0070	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	35.000 T				
0080	403.210 HOT MIX ASPHALT 9.5 MM	1410.000 T				
0090	409.15 BITUMINOUS TACK COAT - APPLIED	1280.000 G				
0100	411.12 CRUSHED STONE SURFACE	100.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015107.00

PROJECT(S): BR-1510(700)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0120	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP	LUMP			
0130	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0140	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			
0150	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	16700.000 LB				
0160	503.13 REINFORCING STEEL, PLACING	16700.000 LB				
0170	504.70 STRUCTURAL STEEL FABRICATED AND DELIVERED	LUMP	LUMP			
0180	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			
0190	505.08 SHEAR CONNECTORS	LUMP	LUMP			
0200	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP	LUMP			
0210	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015107.00

PROJECT(S): BR-1510(700)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	512.081 FRENCH DRAINS	LUMP	LUMP			
0230	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0240	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0250	523.52 BEARING INSTALLATION	10.000 EA				
0260	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	10.000 EA				
0270	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0280	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				
0290	527.34 WORK ZONE CRASH CUSHIONS	2.000 UN				
0300	603.165 15 INCH REINFORCED CONCRETE PIPE CLASS III	60.000 LF				
0310	604.09 CATCH BASIN TYPE B1	2.000 EA				
0320	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015107.00

PROJECT(S): BR-1510(700)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	950.000 LF				
0340	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	25.000 LF				
0350	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA				
0360	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0370	606.363 GUARDRAIL REMOVE AND DISPOSE	430.000 LF				
0380	606.79 GUARDRAIL 350 FLARED TERMINAL	3.000 EA				
0390	607.17 CHAIN LINK FENCE - 6 FOOT	35.000 LF				
0400	607.25 REMOVE AND RESET CHAIN LINK FENCE	450.000 LF				
0410	609.31 CURB TYPE 3	300.000 LF				
0420	610.08 PLAIN RIPRAP	60.000 CY				
0430	610.18 STONE DITCH PROTECTION	80.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015107.00

PROJECT(S): BR-1510(700)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	613.319 EROSION CONTROL BLANKET	40.000 SY				
0450	615.07 LOAM	390.000 CY				
0460	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	75.000 UN				
0470	619.1401 EROSION CONTROL MIX	11.000 CY				
0480	620.58 EROSION CONTROL GEOTEXTILE	225.000 SY				
0490	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	6000.000 LF				
0500	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0510	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0520	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0530	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0540	636.40 MECHANICALLY STABILIZED EARTH RETAINING WALL	8740.000 SF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015107.00

PROJECT(S): BR-1510(700)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	639.18 FIELD OFFICE TYPE A	1.000 EA				
0560	645.251 ROADSIDE GUIDE SIGNS	50.000 SF				
0570	645.271 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS, TYPE I	50.000 SF				
0580	652.31 TYPE I BARRICADE	10.000 EA				
0590	652.33 DRUM	10.000 EA				
0600	652.34 CONE	30.000 EA				
0610	652.35 CONSTRUCTION SIGNS	60.000 SF				
0620	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0630	652.38 FLAGGER	700.000 HR				
0640	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0650	659.10 MOBILIZATION	LUMP	LUMP			



SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015107.00

PROJECT(S): BR-1510(700)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0660	660.21 ON-THE-JOB TRAINING (BID)	1000.000 HR				
	SECTION 0001 TOTAL					
	TOTAL BID					