

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015143.00

PROJECT(S): STP-1514(300)X  
BR-A562(000)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 COMMON ITEMS						
0010	201.23 REMOVING SINGLE TREE TOP ONLY	2.000 EA				
0020	201.24 REMOVING STUMP	2.000 EA				
0030	202.08 REMOVING BUILDING NO.: 1	LUMP	LUMP			
0040	202.08 REMOVING BUILDING NO.: 2	LUMP	LUMP			
0050	202.10 REMOVING EXISTING SUPERSTRUCTURE (PROPERTY OF CONTRACTOR)	LUMP	LUMP			
0060	202.121 REMOVING EXISTING CONCRETE	LUMP	LUMP			
0070	202.15 REMOVING MANHOLE OR CATCH BASIN	7.000 EA				
0080	203.20 COMMON EXCAVATION	5940.000 CY				
0090	203.21 ROCK EXCAVATION	120.000 CY				
0100	203.2312 HEALTH AND SAFETY PLAN	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015143.00

PROJECT(S): STP-1514(300)X  
BR-A562(000)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	203.25 GRANULAR BORROW	635.000 CY				
0120	203.4339 GEOFOAM LIGHTWEIGHT FILL	17.000 CY				
0130	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	50.000 CY				
0140	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	15.000 CY				
0150	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	1000.000 CY				
0160	304.09 AGGREGATE BASE COURSE - CRUSHED	2210.000 CY				
0170	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	3310.000 CY				
0180	403.207 HOT MIX ASPHALT 19.0 MM HMA	900.000 T				
0190	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	650.000 T				
0200	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	300.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015143.00

PROJECT(S): STP-1514(300)X  
BR-A562(000)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	403.213 HOT MIX ASPHALT 12.5 MM BASE	890.000 T				
0220	409.15 BITUMINOUS TACK COAT - APPLIED	478.000 G				
0230	419.20 SAWING, SEALING JOINTS IN BITUMINOUS CONCRETE SURFACE	92.000 LF				
0240	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0250	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP	LUMP			
0260	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0270	502.341 STRUCTURAL CONCRETE ROADWAY MEDIAN	12.000 CY				
0280	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP	LUMP			
0290	502.56 CONCRETE FILL	155.000 CY				
0300	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	91200.000 LB				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015143.00

PROJECT(S): STP-1514(300)X  
BR-A562(000)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0310	503.13 REINFORCING STEEL, PLACING	91200.000 LB				
0320	503.17 MECHANICAL WELDED SPLICE	644.000 EA				
0330	503.30 CORROSION RESISTANT REINFORCING SYSTEM, FABRICATED AND DELIVERED	6900.000 LB				
0340	503.31 CORROSION RESISTANT REINFORCING SYSTEM, PLACING	6900.000 LB				
0350	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP	LUMP			
0360	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			
0370	505.08 SHEAR CONNECTORS	LUMP	LUMP			
0380	506.9102 ZINC RICH COATING SYSTEM (SHOP APPLIED)	LUMP	LUMP			
0390	507.0811 STEEL BRIDGE RAILING, 2 BAR	LUMP	LUMP			
0400	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015143.00

PROJECT(S): STP-1514(300)X  
BR-A562(000)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0410	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0420	510.12 SPECIAL DETOUR FOOT ROADWAY WIDTH, VEHICULAR AND PEDESTRIAN TRAFFIC SEPARATED 12 FT	LUMP	LUMP			
0430	511.07 COFFERDAM: ABUTMENT NO.1	LUMP	LUMP			
0440	511.07 COFFERDAM: ABUTMENT NO.2	LUMP	LUMP			
0450	511.07 COFFERDAM: PIER	LUMP	LUMP			
0460	512.081 FRENCH DRAINS	LUMP	LUMP			
0470	513.09 SLOPE PROTECTION - PORTLAND CEMENT CONCRETE	SY	190.000			
0480	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	SY	340.000			
0490	518.60 REPAIR OF VERTICAL SURFACES < 7.9 IN.	SF	120.000			
0500	518.61 REPAIR OF VERTICAL SURFACES > 7.9 IN.	CY	1.000			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015143.00

PROJECT(S): STP-1514(300)X  
BR-A562(000)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0510	520.232 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	94.000 LF				
0520	523.52 BEARING INSTALLATION	12.000 EA				
0530	523.5401 LAMINATED ELASTOMERIC BEARINGS, FIXED	6.000 EA				
0540	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	6.000 EA				
0550	525.61 EXISTING GRANITE WALL REPAIR	LUMP	LUMP			
0560	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0570	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				
0580	527.303 ENERGY ABSORBING SYSTEM (ET-PLUS)	1.000 EA				
0590	527.305 QUADGUARD CRASH CUSHION	1.000 UN				
0600	527.34 WORK ZONE CRASH CUSHIONS	6.000 UN				
0610	603.159 12 INCH CULVERT PIPE OPTION III	48.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015143.00

PROJECT(S): STP-1514(300)X  
BR-A562(000)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0620	603.179 18 INCH CULVERT PIPE OPTION III	440.000 LF				
0630	604.072 CATCH BASIN TYPE A1-C	6.000 EA				
0640	604.092 CATCH BASIN TYPE B1-C	27.380 EA				
0650	604.164 REBUILDING CATCH BASIN	2.000 EA				
0660	604.247 CATCH BASIN TYPE F5-C	2.000 EA				
0670	604.262 CATCH BASIN TYPE B5-C	2.880 EA				
0680	605.09 6 INCH UNDERDRAIN TYPE B	860.000 LF				
0690	605.11 12 INCH UNDERDRAIN TYPE C	1480.000 LF				
0700	605.13 18 INCH UNDERDRAIN TYPE C	230.000 LF				
0710	606.1721 BRIDGE TRANSITION - TYPE 1	3.000 EA				
0720	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	62.500 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015143.00

PROJECT(S): STP-1514(300)X  
BR-A562(000)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0730	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL WITH RUB RAIL	50.000 LF				
0740	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	8.640 LF				
0750	606.232 GUARDRAIL TYPE 3C - OVER 15 FOOT RADIUS	62.500 LF				
0760	606.2602 TERMINAL END - TRAILING END	2.000 EA				
0770	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	14.000 EA				
0780	606.362 GUARDRAIL ADJUSTED	49.240 LF				
0790	606.79 GUARDRAIL 350 FLARED TERMINAL	3.000 EA				
0800	607.22 CEDAR RAIL FENCE	170.000 LF				
0810	608.26 CURB RAMP DETECTABLE WARNING FIELD	16.000 SF				
0820	609.19 VERTICAL CURB TYPE 2	130.000 LF				
0830	609.20 VERTICAL CURB, CIRCULAR, TYPE 2	61.000 LF				



SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015143.00

PROJECT(S): STP-1514(300)X  
BR-A562(000)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0840	609.244 TERMINAL CURB TYPE 2 - 4 FOOT	4.000 EA				
0850	609.247 TERMINAL CURB TYPE 2 - 7 FOOT	9.000 EA				
0860	609.31 CURB TYPE 3	2486.000 LF				
0870	610.08 PLAIN RIPRAP	302.500 CY				
0880	610.18 STONE DITCH PROTECTION	49.000 CY				
0890	613.319 EROSION CONTROL BLANKET	256.000 SY				
0900	615.07 LOAM	272.000 CY				
0910	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	3.500 UN				
0920	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	11.500 UN				
0930	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	30.000 UN				
0940	618.15 TEMPORARY SEEDING	5.700 LB				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015143.00

PROJECT(S): STP-1514(300)X  
BR-A562(000)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0950	619.1201 MULCH - PLAN QUANTITY	45.500 UN				
0960	619.1401 EROSION CONTROL MIX	50.000 CY				
0970	620.58 EROSION CONTROL GEOTEXTILE	460.000 SY				
0980	620.6012 HDPE GEOMEMBRANE	320.000 SY				
0990	621.037 EVERGREEN TREES (5 FOOT - 6 FOOT) GROUP A	6.000 EA				
1000	621.184 MEDIUM DECIDUOUS TREES (8 FOOT - 10 FOOT) GROUP A	12.000 EA				
1010	621.273 LARGE DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP A	1.000 EA				
1020	621.395 DWARF EVERGREENS (18 INCH - 24 INCH) GROUP A	24.000 EA				
1030	621.413 DWARF EVERGREENS (3 FOOT - 3.50 FOOT) GROUP A	36.000 EA				
1040	621.54 DECIDUOUS SHRUBS (18 INCH - 24 INCH) GROUP A	48.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015143.00

PROJECT(S): STP-1514(300)X  
BR-A562(000)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1050	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	8260.000 LF				
1060	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	380.000 SF				
1070	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
1080	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
1090	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	10.000 HR				
1100	631.11 AIR TOOL (INCLUDING OPERATOR)	10.000 HR				
1110	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
1120	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	20.000 HR				
1130	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
1140	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR				
1150	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	10.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015143.00

PROJECT(S): STP-1514(300)X  
BR-A562(000)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1160	631.22 FRONT END LOADER (INCLUDING OPERATOR)	20.000 HR				
1170	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	20.000 HR				
1180	637.071 DUST CONTROL	LUMP	LUMP			
1190	639.18 FIELD OFFICE TYPE A	1.000 EA				
1200	652.31 TYPE I BARRICADE	2.000 EA				
1210	652.33 DRUM	58.000 EA				
1220	652.34 CONE	58.000 EA				
1230	652.35 CONSTRUCTION SIGNS	700.000 SF				
1240	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
1250	652.38 FLAGGER	4000.000 HR				
1260	653.22 2 INCH POLYSTYRENE PLASTIC INSULATION	12.000 SY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015143.00

PROJECT(S): STP-1514(300)X  
BR-A562(000)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1270	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
1280	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	46.000 SY				
1290	659.10 MOBILIZATION	LUMP	LUMP			
1300	660.21 ON-THE-JOB TRAINING (BID)	1000.000 HR				
SECTION 0001 TOTAL						.
SECTION 0002 ALTERNATE 1 - CONCRETE BLOCK WALL ALT GROUP AW1						
1310	635.31 PREFAB CONCRETE BLOCK GRAVITY WALL	1170.000 SF				
SECTION 0002 TOTAL						.
SECTION 0003 ALTERNATE 2 - AGGREGATE FILLED WALL ALT GROUP AW2						
1320	635.40 PRECAST AGGREGATE FILLED CONCRETE BLOCK GRAVITY WALL	1170.000 SF				
SECTION 0003 TOTAL						.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015143.00

PROJECT(S): STP-1514(300)X  
BR-A562(000)E

CONTRACTOR : \_\_\_\_\_

SECTION 0004 TOWN OF DIXFIELD - UTILITIES

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1330	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	4.000 EA				
1340	801.13 SEWER FORCE MAIN TEMPORARY	LUMP	LUMP			
1350	801.51 DEMOLISH EXISTING FORCE MAIN	LUMP	LUMP			
1360	822.301 PRE-INSULATED DUCTILE IRON PIPE	155.000 LF				
1370	822.35 10 INCH CLASS 52 DUCTILE IRON PIPE	225.000 LF				
1380	825.324 BLOW OFF CHAMBER RECONNECTION	LUMP	LUMP			
1390	827.331 TRENCH INSULATION	90.000 SY				
1400	833.313 AIR RELEASE ASSEMBLY MODIFY AT LEAVITT ST.	1.000 EA				
1410	845.10 STRUCTURAL STEEL UTILITY SUPPORT	LUMP	LUMP			
	SECTION 0004 TOTAL					
	TOTAL BID					