

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015214.00

PROJECTS

015214.00

COUNTY : KENNEBEC

CONTRACT ID : 015214.00

AUGUSTA, HIGHWAY RECONSTRUCTION. WORK INCLUDES CONY CIRCLE RECONSTRUCTION; INTERSECTION, DRAINAGE, AND SAFETY IMPROVEMENTS; AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	05/22/09	\$ 750.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015214.00

PROJECT(S): 015214.00

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS (BASIS OF AWARD)						
0010	201.23 REMOVING SINGLE TREE TOP ONLY	EA 6.000				
0020	201.24 REMOVING STUMP	EA 6.000				
0030	202.15 REMOVING MANHOLE OR CATCH BASIN	EA 9.000				
0040	202.202 REMOVING PAVEMENT SURFACE	SY 7410.000				
0050	202.203 PAVEMENT BUTT JOINTS	SY 630.000				
0060	203.20 COMMON EXCAVATION	CY 5000.000				
0070	203.2333 DISPOSAL OF SPECIAL EXCAVATION	T 20.000				
0080	203.24 COMMON BORROW	CY 950.000				
0090	203.25 GRANULAR BORROW	CY 250.000				
0100	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY 2450.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015214.00

PROJECT(S): 015214.00

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	1100.000 T				
0120	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	302.000 T				
0130	403.211 HOT MIX ASPHALT (SHIMMING)	40.000 T				
0140	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	830.000 T				
0150	409.15 BITUMINOUS TACK COAT - APPLIED	710.000 G				
0160	502.341 STRUCTURAL CONCRETE ROADWAY MEDIAN	50.000 CY				
0170	502.56 CONCRETE FILL	185.000 CY				
0180	603.155 12 INCH REINFORCED CONCRETE PIPE CLASS III	301.000 LF				
0190	603.159 12 INCH CULVERT PIPE OPTION III	152.000 LF				
0200	603.165 15 INCH REINFORCED CONCRETE PIPE CLASS III	10.000 LF				
0210	603.169 15 INCH CULVERT PIPE OPTION III	13.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015214.00

PROJECT(S): 015214.00

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	603.179 18 INCH CULVERT PIPE OPTION III	18.000 LF				
0230	603.209 30 INCH CULVERT PIPE OPTION III	11.000 LF				
0240	604.072 CATCH BASIN TYPE A1-C	10.000 EA				
0250	604.076 60 INCH CATCH BASIN TYPE A1-C	2.000 EA				
0260	604.092 CATCH BASIN TYPE B1-C	7.000 EA				
0270	604.15 MANHOLE	2.000 EA				
0280	604.153 60 INCH MANHOLE	2.000 EA				
0290	604.16 ALTERING CATCH BASIN TO MANHOLES	2.000 EA				
0300	604.164 REBUILDING CATCH BASIN	11.000 EA				
0310	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	6.000 EA				
0320	604.252 CATCH BASIN TYPE A5-C	6.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015214.00

PROJECT(S): 015214.00

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	604.262 CATCH BASIN TYPE B5-C	1.000 EA				
0340	605.11 12 INCH UNDERDRAIN TYPE C	610.000 LF				
0350	605.17 30 INCH UNDERDRAIN TYPE C	360.000 LF				
0360	608.08 REINFORCED CONCRETE SIDEWALK	271.000 SY				
0370	608.26 CURB RAMP DETECTABLE WARNING FIELD	410.000 SF				
0380	609.11 VERTICAL CURB TYPE 1	1210.000 LF				
0390	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	355.000 LF				
0400	609.234 TERMINAL CURB TYPE 1 - 4 FOOT	29.000 EA				
0410	609.237 TERMINAL CURB TYPE 1 - 7 FOOT	26.000 EA				
0420	609.2371 TERMINAL CURB TYPE 1- 7 FT - CIRCULAR	11.000 EA				
0430	609.31 CURB TYPE 3	225.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015214.00

PROJECT(S): 015214.00

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	609.34 CURB TYPE 5	200.000 LF				
0450	609.35 CURB TYPE 5 - CIRCULAR	160.000 LF				
0460	609.38 RESET CURB TYPE 1	1030.000 LF				
0470	609.40 RESET CURB TYPE 5	1675.000 LF				
0480	613.319 EROSION CONTROL BLANKET	120.000 SY				
0490	615.0701 LOAM - PLAN QUANTITY	500.000 CY				
0500	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	41.000 UN				
0510	619.1201 MULCH - PLAN QUANTITY	41.000 UN				
0520	622.10 TRANSPLANTING SHRUB	50.000 EA				
0530	626.11 PRECAST CONCRETE JUNCTION BOX	8.000 EA				
0540	626.21 METALLIC CONDUIT	450.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015214.00

PROJECT(S): 015214.00

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	626.22 NON-METALLIC CONDUIT	350.000 LF				
0560	626.31 18 INCH FOUNDATION	13.000 EA				
0570	626.32 24 INCH FOUNDATION	8.000 EA				
0580	626.331 36 INCH FOUNDATION	4.000 EA				
0590	626.35 CONTROLLER CABINET FOUNDATION	1.000 EA				
0600	626.36 REMOVE OR MODIFY CONCRETE FOUNDATION	1.000 EA				
0610	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	10000.000 LF				
0620	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	1890.000 SF				
0630	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0640	627.77 REMOVING PAVEMENT MARKINGS	600.000 SF				
0650	627.94 PREFORMED THERMOPLASTIC PAVEMENT MARKING	2030.000 SF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015214.00

PROJECT(S): 015214.00

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0660	627.95 STREETPRINT DURATHERM PAVEMENT MARKING	5360.000 SF				
0670	629.05 HAND LABOR, STRAIGHT TIME	80.000 HR				
0680	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR				
0690	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	50.000 HR				
0700	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR				
0710	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	10.000 HR				
0720	631.22 FRONT END LOADER (INCLUDING OPERATOR)	25.000 HR				
0730	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR				
0740	636.63 SEGMENTAL RETAINING WALL - SUPPLIER DESIGN - 4' OR LESS	360.000 SF				
0750	639.18 FIELD OFFICE TYPE A	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015214.00

PROJECT(S): 015214.00

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0760	643.6001 SOLAR POWERED LED PED CROSSWALK BEACON	2.000 EA				
0770	643.80 TRAFFIC SIGNALS AT STONE ST. W/ HANNAFORD	LUMP	LUMP			
0780	643.83 VIDEO DETECTION SYSTEM	LUMP	LUMP			
0790	643.86 TRAFFIC SIGNAL LOOP DETECTORS	1.000 EA				
0800	643.91 MAST ARM POLE	4.000 EA				
0810	643.92 PEDESTAL POLE	1.000 EA				
0820	645.103 DEMOUNT GUIDE SIGN	4.000 EA				
0830	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	33.000 EA				
0840	645.108 DEMOUNT POLE	8.000 EA				
0850	645.113 REINSTALL GUIDE SIGN	3.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015214.00

PROJECT(S): 015214.00

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0860	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	EA 23.000				
0870	645.118 REINSTALL POLE	EA 6.000				
0880	645.161 BREAKAWAY DEVICES SINGLE POLE	EA 6.000				
0890	645.251 ROADSIDE GUIDE SIGNS	SF 502.000				
0900	645.271 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS, TYPE I	SF 357.000				
0910	645.289 STEEL H-BEAM POLES	LB 3900.000				
0920	652.31 TYPE I BARRICADE	EA 15.000				
0930	652.311 TYPE II BARRICADE	EA 5.000				
0940	652.33 DRUM	EA 100.000				
0950	652.34 CONE	EA 100.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015214.00

PROJECT(S): 015214.00

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0960	652.35 CONSTRUCTION SIGNS	1000.000 SF				
0970	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	90.000 CD				
0980	652.38 FLAGGER	5400.000 HR				
0990	652.381 TRAFFIC OFFICERS	250.000 HR				
1000	652.41 PORTABLE - CHANGEABLE MESSAGE SIGN	3.000 EA				
1010	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
1020	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	93.000 SY				
1030	659.10 MOBILIZATION	LUMP	LUMP			
1040	801.17 8 INCH PVC SANITARY SEWER (SDR-35)	46.000 LF				
1050	803.16 4 FOOT DIAMETER PRECAST SEWER MANHOLE	2.000 EA				
1060	822.34 8 INCH CLASS 52 DUCTILE IRON PIPE	64.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015214.00

PROJECT(S): 015214.00

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1070	823.3251 8 INCH GATE VALVE WITH BOX	1.000 EA				
1080	823.332 GATE VALVE BOX, ADJUST TO GRADE	9.000 EA				
	SECTION 0001 TOTAL					.
SECTION 0002 UTILITY ITEM						
1090	812.162 ADJUSTING SEWER MANHOLE TO GRADE	11.000 EA				
	SECTION 0002 TOTAL					
	TOTAL BID					

