

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015603.00

PROJECTS

BR-1560(300)X

COUNTY : ANDROSCOGGIN

CONTRACT ID : 015603.00

SCOPE OF WORK: RUNAROUND POND BRIDGE REPLACEMENT AND OTHER INCIDENTAL WORK. IN ANDROSCOGGIN COUNTY, PROJECT IS LOCATED ON RUNAROUND POND ROAD OVER RUNAROUND POND OUTLET APPROXIMATELY 0.2 MILES WEST OF DAVIS ROAD JUNCTION.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	09/04/10	\$ 400.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015603.00

PROJECT(S): BR-1560(300)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.203 PAVEMENT BUTT JOINTS	300.000 SY				
0020	203.20 COMMON EXCAVATION	1800.000 CY				
0030	203.24 COMMON BORROW	280.000 CY				
0040	203.25 GRANULAR BORROW	280.000 CY				
0050	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	50.000 CY				
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	470.000 CY				
0070	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	70.000 T				
0080	403.213 HOT MIX ASPHALT 12.5 MM BASE	100.000 T				
0090	409.15 BITUMINOUS TACK COAT - APPLIED	100.000 G				
0100	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015603.00

PROJECT(S): BR-1560(300)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			
0120	534.71 PRECAST CONCRETE BOX CULVERT	LUMP	LUMP			
0130	606.36 GUARDRAIL REMOVED AND RESET	250.000 LF				
0140	610.08 PLAIN RIPRAP	70.000 CY				
0150	619.1401 EROSION CONTROL MIX	50.000 CY				
0160	620.58 EROSION CONTROL GEOTEXTILE	109.000 SY				
0170	629.05 HAND LABOR, STRAIGHT TIME	8.000 HR				
0180	631.11 AIR TOOL (INCLUDING OPERATOR)	8.000 HR				
0190	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	8.000 HR				
0200	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	16.000 HR				
0210	652.35 CONSTRUCTION SIGNS	256.000 SF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015603.00

PROJECT(S): BR-1560(300)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	39.000 CD				
0230	652.38 FLAGGER	60.000 HR				
0240	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0250	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

