

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 01560700

PROJECTS

-----

015607.00

COUNTY : OXFORD

CONTRACT ID : 01560700

BRIDGE CULVERT REPLACEMENT

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	06/26/10	0 CALENDAR DAYS \$ 0.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 01560700

PROJECT(S): 015607.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.23 REMOVING SINGLE TREE TOP ONLY	2.000 EA				
0020	201.24 REMOVING STUMP	2.000 EA				
0030	202.202 REMOVING PAVEMENT SURFACE	1180.000 SY				
0040	203.2001 COMMON EXCAVATION - PLAN QUANTITY	276.000 CY				
0050	203.25 GRANULAR BORROW	138.000 CY				
0060	304.104 AGGREGATE SUBBASE COURSE (PLAN QUANTITY)	270.000 CY				
0070	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	100.000 T				
0080	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	40.000 T				
0090	403.213 HOT MIX ASPHALT 12.5 MM BASE	220.000 T				
0100	409.15 BITUMINOUS TACK COAT - APPLIED	80.000 G				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 01560700

PROJECT(S): 015607.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	40.000 CY				
0120	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			
0130	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			
0140	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0150	534.7102 PRECAST STRUCTURAL CONCRETE - DISTRIBUTION SLAB	LUMP	LUMP			
0160	603.15 12 INCH CULVERT PIPE OPTION I	96.000 LF				
0170	604.072 CATCH BASIN TYPE A1-C	2.000 EA				
0180	604.252 CATCH BASIN TYPE A5-C	1.000 EA				
0190	605.11 12 INCH UNDERDRAIN TYPE C	100.000 LF				
0200	606.24 GUARDRAIL TYPE 3D - SINGLE RAIL	350.000 LF				
0210	606.242 GUARDRAIL TYPE 3D - OVER 15 FOOT RADIUS	50.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 01560700

PROJECT(S): 015607.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA				
0230	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0240	606.754 WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	3.000 EA				
0250	606.79 GUARDRAIL 350 FLARED TERMINAL	3.000 EA				
0260	609.11 VERTICAL CURB TYPE 1	147.000 LF				
0270	609.234 TERMINAL CURB TYPE 1 - 4 FOOT	2.000 EA				
0280	609.237 TERMINAL CURB TYPE 1 - 7 FOOT	2.000 EA				
0290	609.38 RESET CURB TYPE 1	150.000 LF				
0300	610.08 PLAIN RIPRAP	40.000 CY				
0310	615.07 LOAM	30.000 CY				
0320	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	2.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 01560700

PROJECT(S): 015607.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	3.000 UN				
0340	619.1201 MULCH - PLAN QUANTITY	5.000 UN				
0350	620.58 EROSION CONTROL GEOTEXTILE	250.000 SY				
0360	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	1780.000 LF				
0370	629.05 HAND LABOR, STRAIGHT TIME	25.000 HR				
0380	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0390	631.14 GRADER (INCLUDING OPERATOR)	15.000 HR				
0400	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR )	10.000 HR				
0410	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0420	631.22 FRONT END LOADER (INCLUDING OPERATOR)	10.000 HR				
0430	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 01560700

PROJECT(S): 015607.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	652.33 DRUM	10.000 EA				
0450	652.34 CONE	10.000 EA				
0460	652.35 CONSTRUCTION SIGNS	540.000 SF				
0470	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	41.000 CD				
0480	652.38 FLAGGER	60.000 HR				
0490	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0500	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

