

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015619.00

PROJECTS

-----  
BH-1561(900)E

COUNTY : OXFORD

CONTRACT ID : 015619.00

SCOPE OF WORK: WILD RIVER BRIDGE REPLACEMENT AND OTHER INCIDENTAL WORK. IN OXFORD COUNTY, PROJECT IS LOCATED ON ROUTE 2 OVER WILD RIVER APPROXIMATELY 0.1 MILES WEST OF ROUTE 113.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	11/18/10	\$ 900.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015619.00

PROJECT(S): BH-1561(900)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.25 GRANULAR BORROW	M3	470.000			
0030	203.25 GRANULAR BORROW FOR UNDERWATER BACKFILL	M3	70.000			
0040	206.10 STRUCTURAL EARTH EXCAVATION - PIERS	M3	750.000			
0050	501.231 DYNAMIC LOADING TEST	EA	3.000			
0060	501.46 STEEL H-BEAM PILES 109 KG/M, DELIVERED	M	275.000			
0070	501.461 STEEL H-BEAM PILES 109 KG/M, IN PLACE	M	275.000			
0080	501.54 STEEL H-BEAM PILES 174 KG/M, DELIVERED	M	295.000			
0090	501.541 STEEL H-BEAM PILES 174 KG/M, IN PLACE	M	295.000			
0100	501.90 PILE TIPS	EA	22.000			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015619.00

PROJECT(S): BH-1561(900)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
0120	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0130	502.239 STRUCTURAL CONCRETE PIERS	LUMP	LUMP			
0140	502.249 STRUCTURAL CONCRETE PIERS (PLACED UNDER WATER)	LUMP	LUMP			
0150	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP	LUMP			
0160	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0170	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP	LUMP			
0180	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	74400.000 KG				
0190	503.13 REINFORCING STEEL, PLACING	74400.000 KG				
0200	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP	LUMP			
0210	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015619.00

PROJECT(S): BH-1561(900)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	505.08 SHEAR CONNECTORS	LUMP	LUMP			
0230	507.0833 MODIFIED WYOMING STEEL BRIDGE RAIL	LUMP	LUMP			
0240	511.07 COFFERDAM: PIER	LUMP	LUMP			
0250	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0260	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0270	520.232 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	24.000 M				
0280	523.52 BEARING INSTALLATION	5.000 EA				
0290	523.5401 LAMINATED ELASTOMERIC BEARINGS, FIXED	5.000 EA				
0300	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				
0310	610.11 STONE BLANKET	145.000 M3				
0320	639.18 FIELD OFFICE TYPE A	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015619.00

PROJECT(S): BH-1561(900)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0340	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

