

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015629.00

PROJECTS

-----  
BR-1562(900)X

COUNTY : AROOSTOOK

CONTRACT ID : 015629.00

IN AROOSTOOK COUNTY, HODGDON STREAM BRIDGE REPLACEMENT  
PROJECT IS LOCATED OVER THE SOUTH BRANCH OF THE MEDUXNEKEAG  
RIVER ON ROUTE 2A APPROXIMATELY 2 MILES SOUTH WEST US1  
JUNCTION.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	12/01/09	\$ 575.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015629.00

PROJECT(S): BR-1562(900)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.127 REMOVE EXISTING BITUMINOUS PAVEMENT	LUMP	LUMP			
0020	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0030	203.20 COMMON EXCAVATION	770.000 CY				
0040	203.24 COMMON BORROW	30.000 CY				
0050	203.26 GRAVEL BORROW	350.000 CY				
0060	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	630.000 CY				
0070	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	30.000 CY				
0080	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	750.000 CY				
0090	403.210 HOT MIX ASPHALT 9.5 MM HMA	250.000 T				
0100	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	150.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015629.00

PROJECT(S): BR-1562(900)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	409.15 BITUMINOUS TACK COAT - APPLIED	80.000 G				
0120	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0130	502.25 STRUCTURAL CONCRETE SUPERSTRUCTURE SLABS	LUMP	LUMP			
0140	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0150	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			
0160	502.56 CONCRETE FILL	35.000 CY				
0170	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	21200.000 LB				
0180	503.13 REINFORCING STEEL, PLACING	21200.000 LB				
0190	503.14 EPOXY COATED REINFORCING STEEL, FABRICATED AND DELIVERED	400.000 LB				
0200	503.15 EPOXY COATED REINFORCING STEEL PLACING	400.000 LB				
0210	507.0811 STEEL BRIDGE RAILING, 2 BAR	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015629.00

PROJECT(S): BR-1562(900)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0230	512.081 FRENCH DRAINS	LUMP	LUMP			
0240	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0250	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	100.000 SY				
0260	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				
0270	535.60 PRESTRESSED STRUCTURAL CONCRETE SLAB	LUMP	LUMP			
0280	605.09 6 INCH UNDERDRAIN TYPE B	25.000 LF				
0290	605.10 6 INCH UNDERDRAIN OUTLET	15.000 LF				
0300	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				
0310	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	56.250 LF				
0320	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	50.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015629.00

PROJECT(S): BR-1562(900)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA				
0340	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	6.000 EA				
0350	606.79 GUARDRAIL 350 FLARED TERMINAL	2.000 EA				
0360	610.08 PLAIN RIPRAP	130.000 CY				
0370	615.07 LOAM	15.000 CY				
0380	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	2.000 UN				
0390	619.1201 MULCH - PLAN QUANTITY	2.000 UN				
0400	619.1401 EROSION CONTROL MIX	25.000 CY				
0410	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	900.000 LF				
0420	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR				
0430	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015629.00

PROJECT(S): BR-1562(900)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				
0450	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR )	20.000 HR				
0460	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0470	635.14 PREFABRICATED CONCRETE MODULAR GRAVITY WALL	900.000 SF				
0480	639.19 FIELD OFFICE TYPE B	1.000 EA				
0490	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0500	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0510	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

