

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015630.00

PROJECTS

BR-A530(000)X

COUNTY : AROOSTOOK

CONTRACT ID : 015630.00

SCOPE OF WORK: VILLAGE BRIDGE REPLACEMENT AND OTHER INCIDENTAL WORK. IN AROOSTOOK COUNTY, PROJECT IS LOCATED ON MAIN STREET OVER THE EAST BRANCH OF THE MATTAWAMKEAG RIVER APPROXIMATELY 100 FEET WEST OF STATION STREET JUNCTION.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	10/15/10	\$ 750.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015630.00

PROJECT(S): BR-A530(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	1250.000 CY				
0030	203.24 COMMON BORROW	180.000 CY				
0040	203.25 GRANULAR BORROW	200.000 CY				
0050	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	355.000 CY				
0060	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	42.000 CY				
0070	304.13 DENSE GRADED CRUSHED AGGREGATE SUBBASE	1475.000 CY				
0080	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	15.000 T				
0090	403.210 HOT MIX ASPHALT 9.5 MM HMA	445.000 T				
0100	409.15 BITUMINOUS TACK COAT - APPLIED	100.000 G				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015630.00

PROJECT(S): BR-A530(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	501.231 DYNAMIC LOADING TEST	1.000 EA				
0120	501.46 STEEL H-BEAM PILES 73 LBS/FT, DELIVERED	90.000 LF				
0130	501.461 STEEL H-BEAM PILES 73 LBS/FT, IN PLACE	90.000 LF				
0140	501.90 PILE TIPS	7.000 EA				
0150	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
0160	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0170	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0180	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			
0190	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	15700.000 LB				
0200	503.13 REINFORCING STEEL, PLACING	15700.000 LB				
0210	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015630.00

PROJECT(S): BR-A530(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0230	511.07 COFFERDAM: ABUTMENT NO. 1	LUMP	LUMP			
0240	511.07 COFFERDAM: ABUTMENT NO. 2	LUMP	LUMP			
0250	512.081 FRENCH DRAINS	LUMP	LUMP			
0260	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0270	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0280	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0290	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				
0300	526.40 RESETTING TEMPORARY CONCRETE BARRIER TYPE I	260.000 LF				
0310	527.303 ENERGY ABSORBING SYSTEM (ET-PLUS)	1.000 EA				
0320	535.62 PRESTRESSED STRUCTURAL CONCRETE BOX BEAM	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015630.00

PROJECT(S): BR-A530(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	603.169 15 INCH CULVERT PIPE OPTION III	130.000 LF				
0340	604.245 CATCH BASIN TYPE F4-C	1.000 EA				
0350	604.247 CATCH BASIN TYPE F5-C	1.000 EA				
0360	604.262 CATCH BASIN TYPE B5-C	1.000 EA				
0370	605.12 15 INCH UNDERDRAIN TYPE C	110.000 LF				
0380	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				
0390	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	175.000 LF				
0400	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0410	606.79 GUARDRAIL 350 FLARED TERMINAL	3.000 EA				
0420	609.11 VERTICAL CURB TYPE 1	17.000 LF				
0430	609.237 TERMINAL CURB TYPE 1 - 7 FOOT	2.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015630.00

PROJECT(S): BR-A530(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	610.08 PLAIN RIPRAP	455.000 CY				
0450	610.18 STONE DITCH PROTECTION	50.000 CY				
0460	613.319 EROSION CONTROL BLANKET	44.000 SY				
0470	615.07 LOAM	30.000 CY				
0480	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	2.000 UN				
0490	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	3.000 UN				
0500	619.12 MULCH	5.000 UN				
0510	619.1401 EROSION CONTROL MIX	15.000 CY				
0520	620.58 NON WOVEN GEOTEXTILE	660.000 SY				
0530	621.101 PLUG/ STARTER PLANT	72.000 EA				
0540	621.279 LARGE DECIDUOUS TREE (2.50 INCH - 3 INCH CALIPER) GROUP A	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015630.00

PROJECT(S): BR-A530(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	621.531 DECIDUOUS SHRUBS (12"-18"CAL.) GROUP A	48.000 EA				
0560	621.546 DECIDUOUS SHRUBS (2 FOOT - 3 FOOT) GROUP A	24.000 EA				
0570	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	2020.000 LF				
0580	629.05 HAND LABOR, STRAIGHT TIME	12.000 HR				
0590	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	12.000 HR				
0600	631.14 GRADER (INCLUDING OPERATOR)	12.000 HR				
0610	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	12.000 HR				
0620	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	12.000 HR				
0630	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	24.000 HR				
0640	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	12.000 HR				
0650	631.22 FRONT END LOADER (INCLUDING OPERATOR)	12.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015630.00

PROJECT(S): BR-A530(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0660	637.071 DUST CONTROL	LUMP	LUMP			
0670	639.18 FIELD OFFICE TYPE A	1.000 EA				
0680	643.72 TEMPORARY TRAFFIC SIGNAL EAST OF VILLAGE BRIDGE	LUMP	LUMP			
0690	643.72 TEMPORARY TRAFFIC SIGNAL WEST OF VILLAGE BRIDGE	LUMP	LUMP			
0700	652.33 DRUM	30.000 EA				
0710	652.34 CONE	30.000 EA				
0720	652.35 CONSTRUCTION SIGNS	145.000 SF				
0730	652.38 FLAGGER	650.000 HR				
0740	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0750	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0760	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015630.00

PROJECT(S): BR-A530(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
	TOTAL BID					

SCHEDULE OF ITEMS

DATE:
REVISED:

CONTRACT ID: 015630.00

PROJECT(S): BR-A530(000)X

LIST ITEMS ON THIS PAGE BY AMENDMENT

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
				.		.
				.		.
				.		.
				.		.
				.		.
				.		.
				.		.
				.		.
				.		.
TOTAL BID				.		.

SPECIAL PROVISIONS ATTACHED