

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015638.00

PROJECTS

-----

015638.00

COUNTY : PISCATAQUIS

CONTRACT ID : 015638.00

BEAVER COVE, MUD BROOK BRIDGE REPLACEMENT. WORK INCLUDES  
MUD BROOK BRIDGE REPLACEMENT AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	09/29/09	\$ 575.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015638.00

PROJECT(S): 015638.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	820.000 CY				
0030	203.231 DISPOSAL OF RIVERBED EXCAVATION	76.000 CY				
0040	203.24 COMMON BORROW	164.000 CY				
0050	203.25 GRANULAR BORROW	140.000 CY				
0060	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	155.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	970.000 CY				
0080	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	128.000 T				
0090	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	128.000 T				
0100	409.15 BITUMINOUS TACK COAT - APPLIED	20.000 G				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015638.00

PROJECT(S): 015638.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	508.13 MEMBRANE WATERPROOFING	LUMP	LUMP			
0120	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			
0130	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			
0140	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0150	534.71 PRECAST CONCRETE BOX CULVERT	LUMP	LUMP			
0160	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	250.000 LF				
0170	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0180	606.79 GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0190	610.08 PLAIN RIPRAP	155.000 CY				
0200	613.319 EROSION CONTROL BLANKET	18.000 SY				
0210	615.0701 LOAM - PLAN QUANTITY	52.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015638.00

PROJECT(S): 015638.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	8.000 UN				
0230	619.1201 MULCH - PLAN QUANTITY	8.000 UN				
0240	619.1401 EROSION CONTROL MIX	50.000 CY				
0250	620.54 STABILIZATION GEOTEXTILE	425.000 SY				
0260	620.58 NON WOVEN GEOTEXTILE	125.000 SY				
0270	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	825.000 LF				
0280	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0290	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0300	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0310	631.14 GRADER (INCLUDING OPERATOR)	10.000 HR				
0320	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR )	10.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015638.00

PROJECT(S): 015638.00

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	10.000 HR				
0340	637.071 DUST CONTROL	LUMP	LUMP			
0350	639.19 FIELD OFFICE TYPE B	1.000 EA				
0360	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP			
0370	652.38 FLAGGER	50.000 HR				
0380	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0390	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0400	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

DATE:  
REVISED:

SCHEDULE OF ITEMS

CONTRACT ID: 015638.00

PROJECT(S): 015638.00

LIST ITEMS ON THIS PAGE BY AMENDMENT

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
TOTAL BID						

SPECIAL PROVISIONS ATTACHED