

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015644.00

PROJECTS

015644.00

COUNTY : PENOBSCOT

CONTRACT ID : 015644.00

ENFIELD, CULVERT REPLACEMENT. WORK INCLUDES KIMBALL BRIDGE
CULVERT REPLACEMENT AND OTHER INCIDENTAL WORK.

SITE		CONTRACT TIME	LIQUIDATED DAMAGES	
CONTRACT	07/31/09		\$	200.00
01		10 CALENDAR DAYS	\$	1500.00
02		INCREMENTAL PERIOD	\$	200.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015644.00

PROJECT(S): 015644.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.20 REMOVING BITUMINOUS CONCRETE PAVEMENT	1760.000 SY				
0020	203.20 COMMON EXCAVATION	700.000 CY				
0030	203.242 DIRTY BORROW	60.000 CY				
0040	203.25 GRANULAR BORROW	470.000 CY				
0050	304.103 AGGREGATE SUBBASE - GRAVEL (TRUCK MEASURE)	600.000 CY				
0060	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	170.000 T				
0070	403.213 HOT MIX ASPHALT 12.5 MM BASE	170.000 T				
0080	409.15 BITUMINOUS TACK COAT - APPLIED	50.000 G				
0090	509.12 STEEL STRUCTURAL PLATE PIPE ARCH:	LUMP	LUMP			
0100	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015644.00

PROJECT(S): 015644.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			
0120	527.303 ENERGY ABSORBING SYSTEM (ET-PLUS)	EA 3.000				
0130	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	LF 662.500				
0140	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	LF 25.000				
0150	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	EA 1.000				
0160	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	EA 4.000				
0170	610.08 PLAIN RIPRAP	CY 40.000				
0180	613.319 EROSION CONTROL BLANKET	SY 100.000				
0190	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	UN 10.000				
0200	619.1201 MULCH - PLAN QUANTITY	UN 10.000				
0210	620.58 NON WOVEN GEOTEXTILE	SY 60.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015644.00

PROJECT(S): 015644.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT		
			DOLLARS	CTS	DOLLARS	CTS	
0220	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP				
0230	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR					
0240	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR					
0250	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR					
0260	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR					
0270	652.312 TYPE III BARRICADE	6.000 EA					
0280	652.33 DRUM	30.000 EA					
0290	652.34 CONE	30.000 EA					
0300	652.35 CONSTRUCTION SIGNS	609.000 SF					
0310	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	14.000 CD					
0320	652.38 FLAGGER	248.000 HR					

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015644.00

PROJECT(S): 015644.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0340	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

SCHEDULE OF ITEMS

DATE:
REVISED:

CONTRACT ID: 015644.00

PROJECT(S): 015644.00

LIST ITEMS ON THIS PAGE BY AMENDMENT

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
			.		.	
			.		.	
			.		.	
			.		.	
			.		.	
			.		.	
			.		.	
TOTAL BID			.		.	

SPECIAL PROVISIONS ATTACHED