

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015851.00

PROJECTS

-----

STP-1585(100)X

STP-1594(300)X

NH-1594(800)E

COUNTY : PENOBSCOT

CONTRACT ID : 015851.00

BANGOR, HIGHWAY RESURFACING. WORK INCLUDES HOT MIX ASPHALT  
OVERLAY, PAVEMENT MILLING, AND OTHER INCIDENTAL WORK.

SITE		CONTRACT TIME	LIQUIDATED DAMAGES	
CONTRACT	10/17/09		\$	750.00
01		INCREMENTAL PERIOD	\$	750.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015851.00

PROJECT(S): STP-1585(100)X  
 STP-1594(300)X  
 NH-1594(800)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.202 REMOVING PAVEMENT SURFACE	96220.000 SY				
0020	202.203 PAVEMENT BUTT JOINTS	2140.000 SY				
0030	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	240.000 T				
0040	403.210 HOT MIX ASPHALT 9.5 MM HMA	9290.000 T				
0050	403.211 HOT MIX ASPHALT (SHIMMING)	760.000 T				
0060	409.15 BITUMINOUS TACK COAT - APPLIED	7640.000 G				
0070	604.167 ALTER CATCH BASIN GRATE TO CASCADE	4.000 EA				
0080	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	21.000 EA				
0090	606.1721 BRIDGE TRANSITION - TYPE 1	8.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015851.00

PROJECT(S): STP-1585(100)X  
 STP-1594(300)X  
 NH-1594(800)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	37.000 LF				
0110	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	37.000 LF				
0120	606.232 GUARDRAIL TYPE 3C - OVER 15 FOOT RADIUS	37.000 LF				
0130	609.31 CURB TYPE 3	400.000 LF				
0140	609.34 CURB TYPE 5	3250.000 LF				
0150	609.35 CURB TYPE 5 - CIRCULAR	200.000 LF				
0160	615.07 LOAM	350.000 CY				
0170	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	25.000 UN				
0180	619.12 MULCH	25.000 UN				
0190	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	97600.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015851.00

PROJECT(S): STP-1585(100)X  
 STP-1594(300)X  
 NH-1594(800)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	SF 5290.000				
0210	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0220	629.05 HAND LABOR, STRAIGHT TIME	HR 15.000				
0230	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	HR 15.000				
0240	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	HR 15.000				
0250	643.86 TRAFFIC SIGNAL LOOP DETECTORS	EA 10.000				
0260	652.33 DRUM	EA 40.000				
0270	652.34 CONE	EA 180.000				
0280	652.35 CONSTRUCTION SIGNS	SF 2012.000				
0290	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	CD 127.200				
0300	652.38 FLAGGER	HR 3290.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015851.00

PROJECT(S): STP-1585(100)X  
 STP-1594(300)X  
 NH-1594(800)E

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0310	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

