

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015853.00

PROJECTS

-----

STP-1585(300)S

COUNTY : PENOBSCOT

CONTRACT ID : 015853.00

BANGOR, HIGHWAY RESURFACING. WORK INCLUDES HIGHWAY  
RESURFACING, DRAINAGE, AND SAFETY IMPROVEMENTS.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	10/17/09	\$ 0.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015853.00

PROJECT(S): STP-1585(300)S

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 HIGHWAY ITEMS						
0010	202.203 PAVEMENT BUTT JOINTS	SY 1075.000				
0020	203.20 COMMON EXCAVATION	CY 790.000				
0030	304.08 AGGREGATE BASE COURSE - SCREENED	CY 155.000				
0040	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY 455.000				
0050	403.207 HOT MIX ASPHALT 19.0 MM HMA	T 140.000				
0060	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	T 20.000				
0070	403.209 HOT MIX ASPHALT 9.5 MM HMA (SIDEWALKS, DRIVES, INCIDENTALS)	T 20.000				
0080	403.210 HOT MIX ASPHALT 9.5 MM HMA	T 1350.000				
0090	403.212 HOT MIX ASPHALT 4.75 MM	T 2000.000				
0100	409.15 BITUMINOUS TACK COAT - APPLIED	G 2300.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015853.00

PROJECT(S): STP-1585(300)S

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	502.3412 STRUCTURAL CONCRETE, RAISED ISLAND	22.000 CY				
0120	604.161 ALTERING CATCH BASIN	1.000 EA				
0130	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	1.000 EA				
0140	605.09 6 INCH UNDERDRAIN TYPE B	656.000 LF				
0150	606.21 GUARDRAIL TYPE 3B - 15 FOOT RADIUS AND LESS	25.000 LF				
0160	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	137.500 LF				
0170	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	25.000 LF				
0180	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	7.000 EA				
0190	606.754 WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	3.000 EA				
0200	606.79 GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0210	609.31 CURB TYPE 3	1110.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015853.00

PROJECT(S): STP-1585(300)S

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	609.38 RESET CURB TYPE 1	700.000 LF				
0230	615.07 LOAM	50.000 CY				
0240	618.13 SEEDING METHOD NUMBER 1	5.000 UN				
0250	619.12 MULCH	5.000 UN				
0260	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	50126.000 LF				
0270	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	2600.000 SF				
0280	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0290	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0300	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0310	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0320	643.71 TRAFFIC SIGNAL MODIFICATION	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015853.00

PROJECT(S): STP-1585(300)S

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	652.33 DRUM	10.000 EA				
0340	652.34 CONE	40.000 EA				
0350	652.35 CONSTRUCTION SIGNS	714.000 SF				
0360	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	46.000 CD				
0370	652.38 FLAGGER	1510.000 HR				
0380	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA				
0390	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

SCHEDULE OF ITEMS

DATE:  
REVISED:

CONTRACT ID: 015853.00

PROJECT(S): STP-1585(300)S

LIST ITEMS ON THIS PAGE BY AMENDMENT

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
				.		.
				.		.
				.		.
				.		.
				.		.
				.		.
				.		.
				.		.
TOTAL BID				.		.

SPECIAL PROVISIONS ATTACHED