

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015929.00

PROJECTS

IM-1592(900)E

COUNTY : KENNEBEC

CONTRACT ID : 015929.00

GARDINER-WEST GARDINER, HIGHWAY RESURFACING. WORK INCLUDES
HOT MIX ASPHALT OVERLAY, PAVMENT MILLING, SAFETY
IMPROVEMENTS, AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	06/07/08	\$ 575.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015929.00

PROJECT(S): IM-1592(900)E

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.202 REMOVING PAVEMENT SURFACE	45000.000 SY				
0020	203.242 DIRTY BORROW	150.000 CY				
0030	205.51 WIDENING OF EXISTING SHOULDER - PLAN QUANTITY	800.000 SY				
0040	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	3500.000 T				
0050	403.210 HOT MIX ASPHALT 9.5 MM HMA	1200.000 T				
0060	403.211 HOT MIX ASPHALT (SHIMMING)	100.000 T				
0070	403.213 HOT MIX ASPHALT 12.5 MM HMA BASE	100.000 T				
0080	409.15 BITUMINOUS TACK COAT - APPLIED	2300.000 G				
0090	424.3331 ASPHALT LOW MODULUS CRACK SEALER, APPLIED	1750.000 LB				
0100	424.3333 LOW MODULUS JOINT SEALER, APPLIED	11300.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015929.00

PROJECT(S): IM-1592(900)E

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	606.1721 BRIDGE TRANSITION - TYPE 1	2.000 EA				
0120	606.1722 BRIDGE TRANSITION - TYPE 2	2.000 EA				
0130	606.178 GUARDRAIL BEAM	125.000 LF				
0140	606.24 GUARDRAIL TYPE 3D - SINGLE RAIL	187.500 LF				
0150	606.35 GUARDRAIL DELINEATOR POST	2.000 EA				
0160	606.352 REFLECTORIZED BEAM GUARDRAIL DELINEATORS	125.000 EA				
0170	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	26.000 EA				
0180	606.362 GUARDRAIL ADJUSTED	1000.000 LF				
0190	606.367 REPLACE UNUSABLE EXISTING GUARDRAIL POSTS	5.000 EA				
0200	606.79 GUARDRAIL 350 FLARED TERMINAL	8.000 EA				
0210	606.792 GUARDRAIL 350 MEDIAN TERMINAL SYSTEM	2.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015929.00

PROJECT(S): IM-1592(900)E

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	609.237 TERMINAL CURB TYPE 1 - 7 FOOT	2.000 EA				
0230	612.06 BITUMINOUS SEALING - BLACK	150.000 SY				
0240	613.319 EROSION CONTROL BLANKET	1500.000 SY				
0250	618.14 SEEDING METHOD NUMBER 2	25.000 UN				
0260	619.12 MULCH	25.000 UN				
0270	627.618 12 INCH SOLID WHITE PAVEMENT MARK LINE	4000.000 LF				
0280	627.72 6 INCH WHITE PAVEMENT MARKING LINE	30000.000 LF				
0290	627.74 6 INCH YELLOW PAVEMENT MARKING LINE	15000.000 LF				
0300	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	50.000 SF				
0310	627.781 TEMPORARY 6 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	45000.000 LF				
0320	629.05 HAND LABOR, STRAIGHT TIME	25.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015929.00

PROJECT(S): IM-1592(900)E

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	50.000 HR				
0340	631.133 SKID STEER (INCLUDING OPERATOR)	25.000 HR				
0350	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	100.000 HR				
0360	645.306 FLEXIBLE REFLECTORIZED DELINEATOR	25.000 EA				
0370	652.30 FLASHING ARROW BOARD	1.000 EA				
0380	652.33 DRUM	150.000 EA				
0390	652.34 CONE	150.000 EA				
0400	652.35 CONSTRUCTION SIGNS	500.000 SF				
0410	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	44.000 CD				
0420	652.38 FLAGGER	100.000 HR				
0430	652.41 PORTABLE - CHANGEABLE MESSAGE SIGN	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015929.00

PROJECT(S): IM-1592(900)E

CONTRACTOR :

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0450	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

