

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 015953.00

PROJECTS

IM-1595(300)E

IM-1595(400)E

IM-1677(500)E

OTHERS

COUNTY : PENOBSCOT

CONTRACT ID : 015953.00

MATTAMISCONTIS TWP - HOWLAND, HIGHWAY RESURFACING. WORK INCLUDES HOT MIX ASPHALT, PAVEMENT MILLING, MISC. BRIDGE IMPROVEMENTS, GUARDRAIL & DRAINAGE IMPROVEMENTS AND OTHER INCIDENTAL WORK.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	07/02/10	\$ 1875.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015953.00

PROJECT(S): IM-1595(300)E
 IM-1595(400)E
 IM-1677(500)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 PROJECT ITEMS

0010	202.205 RUMBLE STRIPS - SHOULDER	379000.000 LF				
0020	205.51 WIDENING OF EXISTING SHOULDER - PLAN QUANTITY	3500.000 SY				
0030	403.102 HOT MIX ASPHALT PAVEMENT - SPECIAL AREAS	225.000 T				
0040	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	56250.000 T				
0050	403.211 HOT MIX ASPHALT (SHIMMING)	27350.000 T				
0060	409.15 BITUMINOUS TACK COAT - APPLIED	51300.000 G				
0070	424.3331 ASPHALT LOW MODULUS CRACK SEALER, APPLIED	31600.000 LB				
0080	424.3333 LOW MODULUS JOINT SEALER, APPLIED	223000.000 LF				
0090	504.069 CONCRETE PIPE TIES	314.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015953.00

PROJECT(S): IM-1595(300)E
 IM-1595(400)E
 IM-1677(500)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	507.08 BRIDGE RAILING	176.000 LF				
0110	507.30 ALUMINUM RAIL BAR SPLICE RETROFIT	16.000 EA				
0120	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0130	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0140	518.39 REPAIRING GRANITE CURB BEDDING MORTAR	140.000 LF				
0150	518.51 REPAIR OF UPWARD FACING SURFACES - BELOW REINFORCING STEEL < 7.9 IN.	1909.000 SF				
0160	518.60 REPAIR OF VERTICAL SURFACES < 7.9 IN.	50.000 SF				
0170	518.61 REPAIR OF VERTICAL SURFACES > 7.9 IN.	15.000 CY				
0180	518.70 REPAIR OF OVERHEAD SURFACES < 7.9 IN.	50.000 SF				
0190	520.242 BRIDGE JOINT MODIFICATION TYPE 2	8.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015953.00

PROJECT(S): IM-1595(300)E
 IM-1595(400)E
 IM-1677(500)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	520.243 BRIDGE JOINT MODIFICATION TYPE 3	2.000 EA				
0210	520.26 LONGITUDINAL BRIDGE JOINT MODIFICATION	25.000 LF				
0220	526.34 PERMANENT CONCRETE TRANSITION BARRIER	12.000 EA				
0230	603.17 18 INCH CULVERT PIPE OPTION I	60.000 LF				
0240	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	150.000 LF				
0250	603.205 30 INCH REINFORCED CONCRETE PIPE CLASS III	58.000 LF				
0260	603.215 36 INCH REINFORCED CONCRETE PIPE CLASS III	30.000 LF				
0270	603.225 42 INCH REINFORCED CONCRETE PIPE CLASS III	50.000 LF				
0280	603.7424 REMOVE & RELAY 24 INCH CONCRETE PIPE	516.000 LF				
0290	603.743 REMOVE & RELAY 30 INCH CONCRETE PIPE	222.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015953.00

PROJECT(S): IM-1595(300)E
 IM-1595(400)E
 IM-1677(500)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0300	603.7436 REMOVE & RELAY 36 INCH CONCRETE PIPE	140.000 LF				
0310	603.7442 REMOVE & RELAY 42 INCH CONCRETE PIPE	58.000 LF				
0320	603.7448 REMOVE & RELAY 48 INCH CONCRETE PIPE	152.000 LF				
0330	603.7454 REMOVE & RELAY 54 INCH CONCRETE PIPE	50.000 LF				
0340	606.1721 BRIDGE TRANSITION - TYPE 1	18.000 EA				
0350	606.178 GUARDRAIL BEAM	1500.000 LF				
0360	606.24 GUARDRAIL TYPE 3D - SINGLE RAIL	2675.000 LF				
0370	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	3.000 EA				
0380	606.35 GUARDRAIL DELINEATOR POST	10.000 EA				
0390	606.352 REFLECTORIZED BEAM GUARDRAIL DELINEATORS	1025.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015953.00

PROJECT(S): IM-1595(300)E
 IM-1595(400)E
 IM-1677(500)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0400	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	156.000 EA				
0410	606.367 REPLACE UNUSABLE EXISTING GUARDRAIL POSTS	35.000 EA				
0420	606.79 GUARDRAIL 350 FLARED TERMINAL	85.000 EA				
0430	610.08 PLAIN RIPRAP	150.000 CY				
0440	610.18 STONE DITCH PROTECTION	25.000 CY				
0450	612.06 BITUMINOUS SEALING - BLACK	250.000 SY				
0460	613.319 EROSION CONTROL BLANKET	4250.000 SY				
0470	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	2575.000 UN				
0480	619.1201 MULCH - PLAN QUANTITY	2575.000 UN				
0490	619.1401 EROSION CONTROL MIX	650.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015953.00

PROJECT(S): IM-1595(300)E
 IM-1595(400)E
 IM-1677(500)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0500	627.618 12 INCH SOLID WHITE PAVEMENT MARK LINE	23700.000 LF				
0510	627.72 6 INCH WHITE PAVEMENT MARKING LINE	455000.000 LF				
0520	627.74 6 INCH YELLOW PAVEMENT MARKING LINE	229000.000 LF				
0530	627.75 WHITE OR YELLOW PAVEMENT AND CURB MARKING	450.000 SF				
0540	627.781 TEMPORARY 6 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	684000.000 LF				
0550	629.05 HAND LABOR, STRAIGHT TIME	250.000 HR				
0560	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	700.000 HR				
0570	631.122 MINI ALL-PURPOSE EXCAVATOR (INCLUDING OPERATOR)	270.000 HR				
0580	631.133 SKID STEER (INCLUDING OPERATOR)	300.000 HR				
0590	631.14 GRADER (INCLUDING OPERATOR)	650.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015953.00

PROJECT(S): IM-1595(300)E
 IM-1595(400)E
 IM-1677(500)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0600	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	1700.000 HR				
0610	631.22 FRONT END LOADER (INCLUDING OPERATOR)	425.000 HR				
0620	639.18 FIELD OFFICE TYPE A	1.000 EA				
0630	639.19 FIELD OFFICE TYPE B	1.000 EA				
0640	645.306 FLEXIBLE REFLECTORIZED DELINEATOR	175.000 EA				
0650	652.30 FLASHING ARROW BOARD	9.000 EA				
0660	652.33 DRUM	1825.000 EA				
0670	652.34 CONE	1800.000 EA				
0680	652.35 CONSTRUCTION SIGNS	7000.000 SF				
0690	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	161.000 CD				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015953.00

PROJECT(S): IM-1595(300)E
 IM-1595(400)E
 IM-1677(500)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0700	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	8.000 EA				
0710	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0720	659.10 MOBILIZATION	LUMP	LUMP			
0730	660.21 ON-THE-JOB TRAINING (BID)	4000.000 HR				
SECTION 0001 TOTAL						.
SECTION 0002 CONTRACTOR RETAIN 10% OF PAVEMENT MILLINGS						
0740	202.202 REMOVING PAVEMENT SURFACE	673000.000 SY				
SECTION 0002 TOTAL						.
SECTION 0003 CONTRACTOR RETAIN 25% OF PAVEMENT MILLINGS						
0750	202.202 REMOVING PAVEMENT SURFACE	673000.000 SY				
SECTION 0003 TOTAL						.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 015953.00

PROJECT(S): IM-1595(300)E
 IM-1595(400)E
 IM-1677(500)E
 OTHERS

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0004 CONTRACTOR RETAIN 50% OF PAVEMENT MILLINGS						
0760	202.202 REMOVING PAVEMENT SURFACE	673000.000 SY				
	SECTION 0004 TOTAL					.
SECTION 0005 CONTRACTOR RETAIN 75% OF PAVEMENT MILLINGS						
0770	202.202 REMOVING PAVEMENT SURFACE	673000.000 SY				
	SECTION 0005 TOTAL					.
SECTION 0006 CONTRACTOR RETAIN 100% OF PAVEMENT MILLINGS						
0780	202.202 REMOVING PAVEMENT SURFACE	673000.000 SY				
	SECTION 0006 TOTAL					
	TOTAL BID					

