

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016685.00

PROJECT(S): BH-1668(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	1300.000 CY				
0030	203.24 COMMON BORROW	10.000 CY				
0040	203.25 GRANULAR BORROW	840.000 CY				
0050	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	10.000 CY				
0060	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	870.000 CY				
0070	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	140.000 CY				
0080	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	1250.000 CY				
0090	403.210 HOT MIX ASPHALT 9.5 MM	114.000 T				
0100	403.213 HOT MIX ASPHALT 12.5 MM BASE	112.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016685.00

PROJECT(S): BH-1668(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	409.15 BITUMINOUS TACK COAT - APPLIED	67.000 G				
0120	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	275.000 CY				
0130	502.22 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS (PLACED UNDER WATER)	200.000 CY				
0140	502.41 STRUCTURAL CONCRETE SUPERSTRUCTURE SLAB	51.000 CY				
0150	502.56 CONCRETE FILL	25.000 CY				
0160	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	30100.000 LB				
0170	503.13 REINFORCING STEEL, PLACING	30100.000 LB				
0180	503.16 WELDED STEEL WIRE FABRIC, COMPLETE IN PLACE	2700.000 LB				
0190	508.13 MEMBRANE WATERPROOFING	LUMP	LUMP			
0200	509.60 FIBERGLASS REINFORCED PLASTIC SHEATHING	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016685.00

PROJECT(S): BH-1668(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	509.74 COMPOSITE ARCH SUPERSTRUCTURE ERECTION, INSTALLATION ONLY	LUMP	LUMP			
0220	511.07 COFFERDAM: ABUTMENT NO. 2	LUMP	LUMP			
0230	511.07 COFFERDAM: ABUTMENT NO.1	LUMP	LUMP			
0240	512.081 FRENCH DRAINS	LUMP	LUMP			
0250	514.06 CURING BOX FOR CONCRETE CYLINDERS	EA 1.000				
0260	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0270	526.30 TEMPORARY CONCRETE BARRIER - TYPE 1	LF 60.000				
0280	603.15 12 INCH CULVERT PIPE OPTION I	LF 60.000				
0290	603.16 15 INCH CULVERT PIPE OPTION I	LF 38.000				
0300	603.17 18 INCH CULVERT PIPE OPTION I	LF 38.000				
0310	604.262 CATCH BASIN TYPE B5-C	EA 1.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016685.00

PROJECT(S): BH-1668(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	605.09 6 INCH UNDERDRAIN TYPE B	192.000 LF				
0330	606.178 GUARDRAIL BEAM	13.000 LF				
0340	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	413.000 LF				
0350	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	50.000 LF				
0360	606.232 GUARDRAIL TYPE 3C - OVER 15 FOOT RADIUS	13.000 LF				
0370	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	8.000 EA				
0380	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	2.000 EA				
0390	606.79 GUARDRAIL 350 FLARED TERMINAL	1.000 EA				
0400	606.80 BURIED-IN-SLOPE GUARDRAIL END	1.000 EA				
0410	609.31 CURB TYPE 3	480.000 LF				
0420	610.08 PLAIN RIPRAP	50.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016685.00

PROJECT(S): BH-1668(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	610.16 HEAVY RIPRAP	335.000 CY				
0440	610.18 STONE DITCH PROTECTION	30.000 CY				
0450	613.319 EROSION CONTROL BLANKET	91.000 SY				
0460	615.07 LOAM	60.000 CY				
0470	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	10.000 UN				
0480	619.1201 MULCH - PLAN QUANTITY	10.000 UN				
0490	619.1401 EROSION CONTROL MIX	120.000 CY				
0500	620.58 EROSION CONTROL GEOTEXTILE	440.000 SY				
0510	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1500.000 LF				
0520	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	6.000 SF				
0530	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016685.00

PROJECT(S): BH-1668(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0550	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				
0560	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	20.000 HR				
0570	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0580	635.14 PREFABRICATED CONCRETE MODULAR GRAVITY WALL	2375.000 SF				
0590	639.18 FIELD OFFICE TYPE A	1.000 EA				
0600	652.31 TYPE I BARRICADE	10.000 EA				
0610	652.312 TYPE III BARRICADE	8.000 EA				
0620	652.33 DRUM	20.000 EA				
0630	652.34 CONE	20.000 EA				
0640	652.35 CONSTRUCTION SIGNS	250.000 SF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016685.00

PROJECT(S): BH-1668(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0650	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0660	652.38 FLAGGER	80.000 HR				
0670	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0680	659.10 MOBILIZATION	LUMP	LUMP			
0690	803.01 TEST PITS	4.000 EA				
0700	841.481 REMOVABLE BOLLARD	2.000 EA				
	SECTION 0001 TOTAL					
	TOTAL BID					