

SCHEDULE OF ITEMS

CONTRACT ID: 016687.00

PROJECT(S): BH-1668(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.23 REMOVING SINGLE TREE TOP ONLY	3.000 EA				
0020	201.24 REMOVING STUMP	2.000 EA				
0030	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0040	203.20 COMMON EXCAVATION	650.000 CY				
0050	203.24 COMMON BORROW	10.000 CY				
0060	203.25 GRANULAR BORROW	165.000 CY				
0070	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	10.000 CY				
0080	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	150.000 CY				
0090	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	740.000 CY				
0100	403.210 HOT MIX ASPHALT 9.5 MM	94.000 T				4

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016687.00

PROJECT(S): BH-1668(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.213 HOT MIX ASPHALT 12.5 MM BASE	96.000 T				
0120	409.15 BITUMINOUS TACK COAT - APPLIED	30.000 G				
0130	501.231 DYNAMIC LOADING TEST	2.000 EA				
0140	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	570.000 LF				
0150	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	525.000 LF				
0160	501.90 PILE TIPS	18.000 EA				
0170	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
0180	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	73.000 CY				
0190	502.22 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS (PLACED UNDER WATER)	141.000 CY				
0200	502.41 STRUCTURAL CONCRETE SUPERSTRUCTURE SLAB	25.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016687.00

PROJECT(S): BH-1668(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	4500.000 LB				
0220	503.13 REINFORCING STEEL, PLACING	4500.000 LB				
0230	503.16 WELDED STEEL WIRE FABRIC, COMPLETE IN PLACE	1200.000 LB				
0240	508.13 MEMBRANE WATERPROOFING	LUMP	LUMP			
0250	509.60 FIBERGLASS REINFORCED PLASTIC SHEATHING	LUMP	LUMP			
0260	509.74 COMPOSITE ARCH SUPERSTRUCTURE ERECTION, INSTALLATION ONLY	LUMP	LUMP			
0270	509.75 COMPOSITE HEADWALL	LUMP	LUMP			
0280	510.10 SPECIAL DETOUR <u>10'</u> ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED	LUMP	LUMP			
0290	511.07 COFFERDAM: ABUTMENT NO.1	LUMP	LUMP			
0300	511.07 COFFERDAM: ABUTMENT NO.2	LUMP	LUMP			
0310	512.081 FRENCH DRAINS	LUMP	LUMP			6

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016687.00

PROJECT(S): BH-1668(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0330	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0340	527.303 ENERGY ABSORBING SYSTEM (ET-PLUS)	1.000 EA				
0350	603.16 15 INCH CULVERT PIPE OPTION I	28.000 LF				
0360	606.17 GUARDRAIL TYPE 3B - SINGLE RAIL	363.000 LF				
0370	606.21 GUARDRAIL TYPE 3B - 15 FOOT RADIUS AND LESS	25.000 LF				
0380	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA				
0390	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0400	606.753 WIDEN SHOULDER FOR LOW VOLUME END	2.000 EA				
0410	606.78 LOW VOLUME GUARDRAIL ENDS - TYPE 3	2.000 EA				
0420	609.31 CURB TYPE 3	86.000 LF				7

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016687.00

PROJECT(S): BH-1668(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	610.08 PLAIN RIPRAP	30.000 CY				
0440	610.16 HEAVY RIPRAP	385.000 CY				
0450	610.18 STONE DITCH PROTECTION	10.000 CY				
0460	613.319 EROSION CONTROL BLANKET	35.000 SY				
0470	615.07 LOAM	51.000 CY				
0480	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	11.000 UN				
0490	619.1201 MULCH - PLAN QUANTITY	11.000 UN				
0500	619.1401 EROSION CONTROL MIX	102.000 CY				
0510	620.58 EROSION CONTROL GEOTEXTILE	370.000 SY				
0520	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1470.000 LF				
0530	629.05 HAND LABOR, STRAIGHT TIME	80.000 HR				8

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016687.00

PROJECT(S): BH-1668(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0550	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				
0560	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	20.000 HR				
0570	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0580	635.14 PREFABRICATED CONCRETE MODULAR GRAVITY WALL	1090.000 SF				
0590	639.18 FIELD OFFICE TYPE A	1.000 EA				
0600	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP			
0610	652.31 TYPE I BARRICADE	20.000 EA				
0620	652.312 TYPE III BARRICADE	7.000 EA				
0630	652.33 DRUM	24.000 EA				
0640	652.34 CONE	35.000 EA				9

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016687.00

PROJECT(S): BH-1668(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0650	652.35 CONSTRUCTION SIGNS	300.000 SF				
0660	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0670	652.38 FLAGGER	240.000 HR				
0680	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0690	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					