

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 016698.00

PROJECTS

BH-1669(800)X

COUNTY : AROOSTOOK

CONTRACT ID : 016698.00

PRESILE BROOK BR REPL AND OTHER INCID WORK

SITE	CONTRACT TIME	LIQUIDATED DAMAGES

CONTRACT	10/15/10	\$ 200.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016698.00

PROJECT(S): BH-1669(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	203.20 COMMON EXCAVATION	450.000 CY				
0020	203.24 COMMON BORROW	10.000 CY				
0030	203.25 GRANULAR BORROW	115.000 CY				
0040	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	420.000 CY				
0050	403.207 HOT MIX ASPHALT 19.0 MM HMA	90.000 T				
0060	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	60.000 T				
0070	409.15 BITUMINOUS TACK COAT - APPLIED	15.000 G				
0080	508.13 MEMBRANE WATERPROOFING	LUMP	LUMP			
0090	511.07 COFFERDAM: Downstream	LUMP	LUMP			
0100	511.07 COFFERDAM: Upstream	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016698.00

PROJECT(S): BH-1669(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0120	534.71 PRECAST CONCRETE BOX CULVERT	LUMP	LUMP			
0130	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	200.000 LF				
0140	606.231 GUARDRAIL TYPE 3C - 15 FOOT RADIUS AND LESS	25.000 LF				
0150	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA				
0160	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	2.000 EA				
0170	606.365 GUARDRAIL REMOVE, MODIFY, AND RESET TYPE 3B TO 3C	50.000 LF				
0180	610.08 PLAIN RIPRAP	140.000 CY				
0190	610.18 STONE DITCH PROTECTION	5.000 CY				
0200	613.319 EROSION CONTROL BLANKET	65.000 SY				
0210	615.07 LOAM	15.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016698.00

PROJECT(S): BH-1669(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	3.000 UN				
0230	619.1201 MULCH - PLAN QUANTITY	3.000 UN				
0240	619.1401 EROSION CONTROL MIX	30.000 CY				
0250	620.58 EROSION CONTROL GEOTEXTILE	230.000 SY				
0260	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	410.000 LF				
0270	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR				
0280	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0290	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	20.000 HR				
0300	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0310	652.312 TYPE III BARRICADE	8.000 EA				
0320	652.33 DRUM	10.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016698.00

PROJECT(S): BH-1669(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	652.34 CONE	20.000 EA				
0340	652.35 CONSTRUCTION SIGNS	500.000 SF				
0350	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0360	652.38 FLAGGER	40.000 HR				
0370	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0380	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					