

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016699.00

PROJECT(S): 016699.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 PROJECT ITEMS

0010	202.19 REMOVING EXISTING BRIDGE	LUMP		LUMP			
0020	203.20 COMMON EXCAVATION	CY	3090.000				
0030	203.2318 DISPOSAL OF SPECIAL WASTE	T	170.000				
0040	203.24 COMMON BORROW	CY	5.000				
0050	203.25 GRANULAR BORROW	CY	650.000				
0060	203.33 SPECIAL FILL	CY	65.000				
0070	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	CY	570.000				
0080	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	CY	10.000				
0090	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	CY	1890.000				
0100	403.207 HOT MIX ASPHALT 19.0 MM HMA	T	630.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016699.00

PROJECT(S): 016699.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	315.000 T				
0120	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	5.000 T				
0130	403.213 HOT MIX ASPHALT 12.5 MM BASE	315.000 T				
0140	409.15 BITUMINOUS TACK COAT - APPLIED	225.000 G				
0150	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0160	511.07 COFFERDAM:	LUMP	LUMP			
0170	526.30 TEMPORARY CONCRETE BARRIER - TYPE 1	60.000 LF				
0180	534.7101 PRECAST CONCRETE BOX CULVERT - STATE SUPPLIED	LUMP	LUMP			
0190	603.2351 48 INCH REINFORCED CONCRETE PIPE CLASS IV	224.000 LF				
0200	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	600.000 LF				
0210	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016699.00

PROJECT(S): 016699.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	606.369 GUARDRAIL REMOVED AND STACKED	200.000 LF				
0230	606.79 GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0240	610.08 PLAIN RIPRAP	375.000 CY				
0250	610.16 HEAVY RIPRAP	40.000 CY				
0260	610.18 STONE DITCH PROTECTION	100.000 CY				
0270	613.319 EROSION CONTROL BLANKET	205.000 SY				
0280	615.07 LOAM	6.000 CY				
0290	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	1.000 UN				
0300	619.1401 EROSION CONTROL MIX	170.000 CY				
0310	620.58 EROSION CONTROL GEOTEXTILE	580.000 SY				
0320	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2100.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016699.00

PROJECT(S): 016699.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0340	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR				
0350	631.13 BULLDOZER (INCLUDING OPERATOR)	20.000 HR				
0360	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				
0370	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	20.000 HR				
0380	631.16 ROLLER, PAVEMENT (INCLUDING OPERATOR)	20.000 HR				
0390	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0400	639.18 FIELD OFFICE TYPE A	1.000 EA				
0410	652.312 TYPE III BARRICADE	6.000 EA				
0420	652.33 DRUM	12.000 EA				
0430	652.34 CONE	24.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016699.00

PROJECT(S): 016699.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	652.35 CONSTRUCTION SIGNS	607.000 SF				
0450	652.38 FLAGGER	100.000 HR				
0460	652.39 WORK ZONE TRAFFIC CONTROL	LUMP	LUMP			
0470	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0480	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					