

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016742.00

PROJECT(S): 016742.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	456.000 CY				
0030	203.21 ROCK EXCAVATION	100.000 CY				
0040	203.25 GRANULAR BORROW	272.000 CY				
0050	203.35 CRUSHED STONE FILL	60.000 CY				
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	547.000 CY				
0070	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	110.000 T				
0080	403.213 HOT MIX ASPHALT 12.5 MM BASE	110.000 T				
0090	409.15 BITUMINOUS TACK COAT - APPLIED	25.000 G				
0100	508.13 MEMBRANE WATERPROOFING	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016742.00

PROJECT(S): 016742.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	511.07 COFFERDAM: DOWNSTREAM	LUMP	LUMP			
0120	511.07 COFFERDAM: UPSTREAM	LUMP	LUMP			
0130	526.30 TEMPORARY CONCRETE BARRIER - TYPE 1	120.000 LF				
0140	534.7101 PRECAST CONCRETE BOX CULVERT - STATE SUPPLIED	LUMP	LUMP			
0150	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	388.000 LF				
0160	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	4.000 EA				
0170	606.78 LOW VOLUME GUARDRAIL ENDS - TYPE 3	4.000 EA				
0180	610.08 PLAIN RIPRAP	194.000 CY				
0190	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	5.000 UN				
0200	619.1401 EROSION CONTROL MIX	55.000 CY				
0210	620.54 STABILIZATION GEOTEXTILE	422.000 SY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016742.00

PROJECT(S): 016742.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	620.58 EROSION CONTROL GEOTEXTILE	193.000 SY				
0230	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	200.000 LF				
0240	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0250	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0260	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	10.000 HR				
0270	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	10.000 HR				
0280	639.19 FIELD OFFICE TYPE B	1.000 EA				
0290	652.312 TYPE III BARRICADE	6.000 EA				
0300	652.33 DRUM	10.000 EA				
0310	652.34 CONE	20.000 EA				
0320	652.35 CONSTRUCTION SIGNS	332.000 SF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016742.00

PROJECT(S): 016742.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	75.000 CD				
0340	652.38 FLAGGER	20.000 HR				
0350	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					