

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 016745.00

PROJECTS

BR-1674(500)S

COUNTY : KNOX

CONTRACT ID : 016745.00

SCOPE OF WORK: SPRUCE HEAD BRIDGE REPLACEMENT AND OTHER INCIDENTAL WORK. IN KNOW COUNTY, PROJECT IS LOCATED ON ISLAND ROAD OVER THE ATLANTIC OCEAN APPROXIMATELY 0.65 OF A MILE SOUTHERLY OF ROUTE 73.

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	06/30/10	\$ 900.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016745.00

PROJECT(S): BR-1674(500)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	550.000 CY				
0030	203.24 COMMON BORROW	1700.000 CY				
0040	203.25 GRANULAR BORROW	550.000 CY				
0050	203.27 ROCK BORROW	200.000 CY				
0060	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	190.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	990.000 CY				
0080	403.210 HOT MIX ASPHALT 9.5 MM HMA	370.000 T				
0090	403.213 HOT MIX ASPHALT 12.5 MM BASE	160.000 T				
0100	409.15 BITUMINOUS TACK COAT - APPLIED	55.000 G				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016745.00

PROJECT(S): BR-1674(500)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	501.231 DYNAMIC LOADING TEST	2.000 EA				
0120	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	335.000 LF				
0130	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	335.000 LF				
0140	501.722 STEEL CASINGS, INSTALLED	175.000 LF				
0150	501.90 PILE TIPS	10.000 EA				
0160	501.902 PIPE PILE - CUTTING TEETH	10.000 EA				
0170	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP	LUMP			
0180	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0190	502.261 STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON CONCRETE BRIDGE	LUMP	LUMP			
0200	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0210	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALK	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016745.00

PROJECT(S): BR-1674(500)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	503.14 EPOXY COATED REINFORCING STEEL, FABRICATED AND DELIVERED	13500.000 LB				
0230	503.15 EPOXY COATED REINFORCING STEEL PLACING	13500.000 LB				
0240	507.0811 STEEL BRIDGE RAILING, 2 BAR	LUMP	LUMP			
0250	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0260	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED	LUMP	LUMP			
0270	512.081 FRENCH DRAINS	LUMP	LUMP			
0280	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0290	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			
0300	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0310	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016745.00

PROJECT(S): BR-1674(500)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	535.61 PRESTRESSED STRUCTURAL CONCRETE I-GIRDERS	LUMP	LUMP			
0330	606.17 GUARDRAIL TYPE 3B - SINGLE RAIL	475.000 LF				
0340	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				
0350	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0360	606.79 GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0370	610.08 PLAIN RIPRAP	225.000 CY				
0380	610.16 HEAVY RIPRAP	1050.100 CY				
0390	613.319 EROSION CONTROL BLANKET	15.000 SY				
0400	615.0701 LOAM - PLAN QUANTITY	40.000 CY				
0410	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	1.000 UN				
0420	619.1201 MULCH - PLAN QUANTITY	2.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016745.00

PROJECT(S): BR-1674(500)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	619.1401 EROSION CONTROL MIX	8.000 CY				
0440	620.58 NON WOVEN GEOTEXTILE	1150.000 SY				
0450	627.711 WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE (PLAN QUANTITY)	1825.000 LF				
0460	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0470	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0480	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0490	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	10.000 HR				
0500	635.14 PREFABRICATED CONCRETE MODULAR GRAVITY WALL	3650.000 SF				
0510	639.18 FIELD OFFICE TYPE A	1.000 EA				
0520	652.312 TYPE III BARRICADE	20.000 EA				
0530	652.33 DRUM	20.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016745.00

PROJECT(S): BR-1674(500)S

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	652.34 CONE	40.000 EA				
0550	652.35 CONSTRUCTION SIGNS	250.000 SF				
0560	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0570	652.38 FLAGGER	200.000 HR				
0580	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0590	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					

SCHEDULE OF ITEMS

DATE:
REVISED:

CONTRACT ID: 016745.00

PROJECT(S): BR-1674(500)S

LIST ITEMS ON THIS PAGE BY AMENDMENT

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
	TOTAL BID					

SPECIAL PROVISIONS ATTACHED