

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016758.00

PROJECT(S): 016758.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	675.000 CY				
0030	203.24 COMMON BORROW	60.000 CY				
0040	203.25 GRANULAR BORROW	210.000 CY				
0050	203.35 CRUSHED STONE FILL	130.000 CY				
0060	204.41 REHABILITATION OF EXISTING SHOULDERS, PLAN QUANTITY	110.000 SY				
0070	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	66.000 CY				
0080	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	210.000 CY				
0090	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	840.000 CY				
0100	403.207 HOT MIX ASPHALT 19.0 MM HMA	120.000 T				4

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016758.00

PROJECT(S): 016758.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	148.000 T				
0120	403.213 HOT MIX ASPHALT 12.5 MM BASE	148.000 T				
0130	409.15 BITUMINOUS TACK COAT - APPLIED	52.000 G				
0140	508.13 MEMBRANE WATERPROOFING	LUMP	LUMP			
0150	511.07 COFFERDAM:	LUMP	LUMP			
0160	526.30 TEMPORARY CONCRETE BARRIER - TYPE 1	80.000 LF				
0170	527.303 ENERGY ABSORBING SYSTEM (ET-PLUS)	2.000 EA				
0180	534.7101 PRECAST CONCRETE BOX CULVERT - STATE SUPPLIED	LUMP	LUMP			
0190	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	388.000 LF				
0200	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	6.000 EA				
0210	606.79 GUARDRAIL 350 FLARED TERMINAL	2.000 EA				5

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016758.00

PROJECT(S): 016758.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	610.08 PLAIN RIPRAP	172.000 CY				
0230	610.18 STONE DITCH PROTECTION	25.000 CY				
0240	615.07 LOAM	30.000 CY				
0250	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	4.000 UN				
0260	619.1201 MULCH - PLAN QUANTITY	4.000 UN				
0270	619.1401 EROSION CONTROL MIX	10.000 CY				
0280	620.54 STABILIZATION GEOTEXTILE	435.000 SY				
0290	620.58 EROSION CONTROL GEOTEXTILE	310.000 SY				
0300	620.65 REINFORCEMENT GEOGRID	192.000 SY				
0310	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1050.000 LF				
0320	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				6

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016758.00

PROJECT(S): 016758.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0340	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	10.000 HR				
0350	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0360	639.19 FIELD OFFICE TYPE B	1.000 EA				
0370	652.312 TYPE III BARRICADE	6.000 EA				
0380	652.33 DRUM	10.000 EA				
0390	652.34 CONE	20.000 EA				
0400	652.35 CONSTRUCTION SIGNS	470.000 SF				
0410	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0420	652.38 FLAGGER	100.000 HR				
0430	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			7

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016758.00

PROJECT(S): 016758.00

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					