

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 016802.00

PROJECTS

-----

NH-1680(200)E

NH-1680(300)X

NH-1680(400)X

COUNTY : WALDO

CONTRACT ID : 016802.00

HIGHWAY MILL AND FILLS

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	09/02/10	\$ 0.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016802.00

PROJECT(S): NH-1680(200)E  
 NH-1680(300)X  
 NH-1680(400)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.202 REMOVING PAVEMENT SURFACE	202369.250 SY				
0020	202.203 PAVEMENT BUTT JOINTS	171.120 SY				
0030	203.242 DIRTY BORROW	300.000 CY				
0040	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	10.000 T				
0050	403.210 HOT MIX ASPHALT 9.5 MM	18950.000 T				
0060	403.211 HOT MIX ASPHALT (SHIMMING)	600.000 T				
0070	409.15 BITUMINOUS TACK COAT - APPLIED	10800.000 G				
0080	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	14.000 CY				
0090	424.3331 ASPHALT LOW MODULUS CRACK SEALER, APPLIED	22650.000 LB				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016802.00

PROJECT(S): NH-1680(200)E  
 NH-1680(300)X  
 NH-1680(400)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	504.07 CONCRETE PIPE TIES	2.000 GP				
0110	603.41 24 INCH REINFORCED CONCRETE PIPE CLASS IV	80.000 LF				
0120	604.164 REBUILDING CATCH BASIN	10.000 EA				
0130	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	2.000 EA				
0140	606.178 GUARDRAIL BEAM	425.000 LF				
0150	606.21 GUARDRAIL TYPE 3B - 15 FOOT RADIUS AND LESS	50.000 LF				
0160	606.22 GUARDRAIL TYPE 3B - OVER 15 FOOT RADIUS	50.000 LF				
0170	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA				
0180	606.352 REFLECTORIZED BEAM GUARDRAIL DELINEATORS	180.000 EA				
0190	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	50.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016802.00

PROJECT(S): NH-1680(200)E  
 NH-1680(300)X  
 NH-1680(400)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	606.367 REPLACE UNUSABLE EXISTING GUARDRAIL POSTS	14.000 EA				
0210	606.79 GUARDRAIL 350 FLARED TERMINAL	5.000 EA				
0220	609.31 CURB TYPE 3	800.000 LF				
0230	610.08 PLAIN RIPRAP	8.000 CY				
0240	613.319 EROSION CONTROL BLANKET	2817.000 SY				
0250	615.07 LOAM	43.000 CY				
0260	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	21.000 UN				
0270	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	210.000 UN				
0280	619.1201 MULCH - PLAN QUANTITY	231.000 UN				
0290	620.58 EROSION CONTROL GEOTEXTILE	16.000 SY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016802.00

PROJECT(S): NH-1680(200)E  
 NH-1680(300)X  
 NH-1680(400)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0300	627.18 12 " SOLID WHITE PAVEMENT MARKING	4145.000 LF				
0310	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	86794.000 LF				
0320	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	866.000 SF				
0330	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0340	627.95 STREETPRINT DURATHERM PAVEMENT MARKING	550.000 SF				
0350	629.05 HAND LABOR, STRAIGHT TIME	110.000 HR				
0360	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	110.000 HR				
0370	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	220.000 HR				
0380	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	8.000 HR				
0390	639.19 FIELD OFFICE TYPE B	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016802.00

PROJECT(S): NH-1680(200)E  
 NH-1680(300)X  
 NH-1680(400)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0400	643.86 TRAFFIC SIGNAL LOOP DETECTORS	2.000 EA				
0410	652.33 DRUM	180.000 EA				
0420	652.34 CONE	440.000 EA				
0430	652.35 CONSTRUCTION SIGNS	3295.000 SF				
0440	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	136.000 CD				
0450	652.38 FLAGGER	3105.000 HR				
0460	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	6.000 EA				
0470	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					