

MAINE DEPARTMENT OF TRANSPORTATION

BID

DATE OF OPENING :

CALL ORDER :

CONTRACT ID : 016810.00

PROJECTS

NH-1681(000)E
STP-1771(700)X
STP-1771(800)X

COUNTY : PENOBSCOT

CONTRACT ID : 016810.00

1 1/4" OVERLAY

SITE	CONTRACT TIME	LIQUIDATED DAMAGES
CONTRACT	10/02/10	\$ 0.00

FOLLOWING GROUPS ARE ALTERNATES :

FOLLOWING ITEMS ARE ALTERNATES :

BIDDERS MUST ENTER ALL UNIT PRICES, MAKE ALL EXTENSIONS AND TOTAL THE BID.

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016810.00

PROJECT(S): NH-1681(000)E
 STP-1771(700)X
 STP-1771(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.202 REMOVING PAVEMENT SURFACE	133000.000 SY				
0020	202.203 PAVEMENT BUTT JOINTS	2110.000 SY				
0030	203.20 COMMON EXCAVATION	1650.000 CY				
0040	203.242 DIRTY BORROW	60.000 CY				
0050	211.22 INSLOPE EXCAVATION - GUARDRAIL	10800.000 LF				
0060	304.103 AGGREGATE SUBBASE - GRAVEL (TRUCK MEASURE)	1900.000 CY				
0070	403.102 HOT MIX ASPHALT PAVEMENT - SPECIAL AREAS	100.000 T				
0080	403.207 HOT MIX ASPHALT 19.0 MM HMA	420.000 T				
0090	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	510.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016810.00

PROJECT(S): NH-1681(000)E
 STP-1771(700)X
 STP-1771(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	403.210 HOT MIX ASPHALT 9.5 MM	25720.000 T				
0110	403.212 HOT MIX ASPHALT 4.75 MM	14730.000 T				
0120	403.213 HOT MIX ASPHALT 12.5 MM BASE	11000.000 T				
0130	409.15 BITUMINOUS TACK COAT - APPLIED	25020.000 G				
0140	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	330.000 CY				
0150	603.179 18 INCH CULVERT PIPE OPTION III	20.000 LF				
0160	603.199 24 INCH CULVERT PIPE OPTION III	20.000 LF				
0170	604.167 ALTER CATCH BASIN GRATE TO CASCADE	1.000 EA				
0180	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	28.000 EA				
0190	604.182 CLEAN EXISTING CATCH BASIN AND MANHOLE	10.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016810.00

PROJECT(S): NH-1681(000)E
 STP-1771(700)X
 STP-1771(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0200	605.09 6 INCH UNDERDRAIN TYPE B	650.000 LF				
0210	605.10 6 INCH UNDERDRAIN OUTLET	60.000 LF				
0220	606.178 GUARDRAIL BEAM	1000.000 LF				
0230	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	88.000 EA				
0240	606.356 UNDERDRAIN DELINEATOR POST	15.000 EA				
0250	606.362 GUARDRAIL ADJUSTED	4000.000 LF				
0260	606.367 REPLACE UNUSABLE EXISTING GUARDRAIL POSTS	80.000 EA				
0270	606.79 GUARDRAIL 350 FLARED TERMINAL	32.000 EA				
0280	609.31 CURB TYPE 3	6366.000 LF				
0290	613.319 EROSION CONTROL BLANKET	6673.000 SY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016810.00

PROJECT(S): NH-1681(000)E
 STP-1771(700)X
 STP-1771(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0300	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	190.000 UN				
0310	619.1201 MULCH - PLAN QUANTITY	190.000 UN				
0320	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0330	629.05 HAND LABOR, STRAIGHT TIME	370.000 HR				
0340	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	90.000 HR				
0350	631.11 AIR TOOL (INCLUDING OPERATOR)	90.000 HR				
0360	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	520.000 HR				
0370	631.14 GRADER (INCLUDING OPERATOR)	160.000 HR				
0380	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	1030.000 HR				
0390	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 016810.00

PROJECT(S): NH-1681(000)E

STP-1771(700)X

STP-1771(800)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0400	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	50.000 HR				
0410	631.50 BUCKET TRUCK CREW	10.000 HR				
0420	639.19 FIELD OFFICE TYPE B	1.000 EA				
0430	652.33 DRUM	250.000 EA				
0440	652.34 CONE	515.000 EA				
0450	652.35 CONSTRUCTION SIGNS	2576.000 SF				
0460	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	179.000 CD				
0470	652.38 FLAGGER	5200.000 HR				
0480	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0490	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					