

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017252.00

PROJECT(S): STP-1725(200)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.203 PAVEMENT BUTT JOINTS	890.000 SY				
0020	203.20 COMMON EXCAVATION	940.000 CY				
0030	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	410.000 CY				
0040	403.1021 TEXTURED ASPHALT PAVEMENT	270.000 SY				
0050	403.207 HOT MIX ASPHALT 19.0 MM HMA	910.000 T				
0060	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	530.000 T				
0070	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	80.000 T				
0080	403.213 HOT MIX ASPHALT 12.5 MM BASE	210.000 T				
0090	409.15 BITUMINOUS TACK COAT - APPLIED	700.000 G				
0100	603.169 15 INCH CULVERT PIPE OPTION III	63.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017252.00

PROJECT(S): STP-1725(200)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	603.1752 18 INCH REINFORCED CONCRETE PIPE CLASS IV	11.000 LF				
0120	603.179 18 INCH CULVERT PIPE OPTION III	3.500 LF				
0130	603.199 24 INCH CULVERT PIPE OPTION III	16.000 LF				
0140	603.41 24 INCH REINFORCED CONCRETE PIPE CLASS IV	3.300 LF				
0150	603.80 24 INCH INLET GRATE UNIT	1.000 EA				
0160	604.092 CATCH BASIN TYPE B1-C	4.000 EA				
0170	604.15 MANHOLE	1.000 EA				
0180	604.16 ALTERING CATCH BASIN TO MANHOLES	3.000 EA				
0190	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	3.000 EA				
0200	608.26 CURB RAMP DETECTABLE WARNING FIELD	24.000 SF				
0210	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	12.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017252.00

PROJECT(S): STP-1725(200)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	609.31 CURB TYPE 3	870.000 LF				
0230	609.34 CURB TYPE 5	660.000 LF				
0240	609.35 CURB TYPE 5 - CIRCULAR	64.000 LF				
0250	609.38 RESET CURB TYPE 1	14.000 LF				
0260	609.40 RESET CURB TYPE 5	430.000 LF				
0270	610.08 PLAIN RIPRAP	4.000 CY				
0280	615.07 LOAM	61.000 CY				
0290	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	5.000 UN				
0300	619.1201 MULCH - PLAN QUANTITY	5.000 UN				
0310	620.58 EROSION CONTROL GEOTEXTILE	24.000 SY				
0320	626.31 18 INCH FOUNDATION	2.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017252.00

PROJECT(S): STP-1725(200)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	4300.000 LF				
0340	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	590.000 SF				
0350	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0360	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0370	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	5.000 HR				
0380	631.11 AIR TOOL (INCLUDING OPERATOR)	5.000 HR				
0390	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0400	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	5.000 HR				
0410	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	8.000 HR				
0420	643.6001 SOLAR POWERED LED PED CROSSWALK BEACON	2.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017252.00

PROJECT(S): STP-1725(200)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	5.000 EA				
0440	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	5.000 EA				
0450	645.271 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS, TYPE I	113.250 SF				
0460	645.306 FLEXIBLE REFLECTORIZED DELINEATOR	35.000 EA				
0470	652.33 DRUM	80.000 EA				
0480	652.34 CONE	80.000 EA				
0490	652.35 CONSTRUCTION SIGNS	360.000 SF				
0500	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0510	652.38 FLAGGER	1200.000 HR				
0520	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017252.00

PROJECT(S): STP-1725(200)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0530	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	180.000 SY				
0540	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					