

SCHEDULE OF ITEMS

CONTRACT ID: 017356.00

PROJECT(S): 01735600

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

0010	202.202 REMOVING PAVEMENT SURFACE	16800.000 SY				
0020	202.203 PAVEMENT BUTT JOINTS	50.000 SY				
0030	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	15.000 T				
0040	403.210 HOT MIX ASPHALT 9.5 MM	1425.000 T				
0050	403.212 HOT MIX ASPHALT 4.75 MM	420.000 T				
0060	409.15 BITUMINOUS TACK COAT - APPLIED	1225.000 G				
0070	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	10.000 CY				
0080	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	5.000 EA				
0090	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	10080.000 LF				
0100	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	550.000 SF				

SCHEDULE OF ITEMS

CONTRACT ID: 017356.00

PROJECT(S): 01735600

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	627.76 TEMPORARY PVMT. MARK LINE, W OR YELLOW	LUMP	LUMP			
0120	629.05 HAND LABOR, STRAIGHT TIME	5.000 HR				
0130	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				
0140	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0150	652.33 DRUM	15.000 EA				
0160	652.34 CONE	100.000 EA				
0170	652.35 CONSTRUCTION SIGNS	650.000 SF				
0180	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	33.000 CD				
0190	652.38 FLAGGER	600.000 HR				
0200	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					