

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017576.00

PROJECT(S): BR-1757(600)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.19 REMOVING EXISTING BRIDGE	LUMP	LUMP			
0020	203.20 COMMON EXCAVATION	570.000 CY				
0030	203.24 COMMON BORROW	5.000 CY				
0040	203.25 GRANULAR BORROW	1230.000 CY				
0050	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	1720.000 CY				
0060	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	150.000 CY				
0070	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	665.000 CY				
0080	403.102 HOT MIX ASPHALT PAVEMENT - SPECIAL AREAS	5.000 T				
0090	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	25.000 T				
0100	403.210 HOT MIX ASPHALT 9.5 MM	263.000 T				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017576.00

PROJECT(S): BR-1757(600)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	403.213 HOT MIX ASPHALT 12.5 MM BASE	194.000 T				
0120	409.15 BITUMINOUS TACK COAT - APPLIED	27.000 G				
0130	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0140	502.22 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS (PLACED U NDER WATER)	610.000 CY				
0150	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP	LUMP			
0160	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0170	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP	LUMP			
0180	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	82200.000 LB				
0190	503.13 REINFORCING STEEL, PLACING	82200.000 LB				
0200	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017576.00

PROJECT(S): BR-1757(600)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			
0220	505.08 SHEAR CONNECTORS	LUMP	LUMP			
0230	507.0811 STEEL BRIDGE RAILING, 2 BAR	LUMP	LUMP			
0240	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP	LUMP			
0250	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0260	511.07 COFFERDAM: ABUTMENT NO. 2	LUMP	LUMP			
0270	511.07 COFFERDAM: ABUTMENT NO.1	LUMP	LUMP			
0280	512.081 FRENCH DRAINS	LUMP	LUMP			
0290	514.06 CURING BOX FOR CONCRETE CYLINDERS	EA 1.000				
0300	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	SY 275.000				
0310	520.21 EXPANSION DEVICE - GLAND SEAL	EA 1.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017576.00

PROJECT(S): BR-1757(600)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	523.52 BEARING INSTALLATION	12.000 EA				
0330	523.5401 LAMINATED ELASTOMERIC BEARINGS, FIXED	6.000 EA				
0340	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	6.000 EA				
0350	526.30 TEMPORARY CONCRETE BARRIER - TYPE 1	60.000 LF				
0360	526.34 PERMANENT CONCRETE TRANSITION BARRIER	4.000 EA				
0370	527.303 ENERGY ABSORBING SYSTEM (ET-PLUS)	2.000 EA				
0380	603.179 18 INCH CULVERT PIPE OPTION III	155.000 LF				
0390	604.092 CATCH BASIN TYPE B1-C	3.000 EA				
0400	604.163 ABANDONING CATCH BASIN	1.000 EA				
0410	605.09 6 INCH UNDERDRAIN TYPE B	212.000 LF				
0420	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017576.00

PROJECT(S): BR-1757(600)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	87.500 LF				
0440	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0450	606.79 GUARDRAIL 350 FLARED TERMINAL	2.000 EA				
0460	608.26 CURB RAMP DETECTABLE WARNING FIELD	23.000 SF				
0470	609.31 CURB TYPE 3	289.000 LF				
0480	610.08 PLAIN RIPRAP	290.000 CY				
0490	610.18 STONE DITCH PROTECTION	10.000 CY				
0500	613.319 EROSION CONTROL BLANKET	25.000 SY				
0510	615.07 LOAM	11.000 CY				
0520	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	1.000 UN				
0530	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	2.000 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017576.00

PROJECT(S): BR-1757(600)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	619.1401 EROSION CONTROL MIX	21.000 CY				
0550	620.58 EROSION CONTROL GEOTEXTILE	385.000 SY				
0560	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1050.000 LF				
0570	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	100.000 SF				
0580	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0590	631.121 HEAVY DUTY ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR				
0600	631.13 BULLDOZER (INCLUDING OPERATOR)	20.000 HR				
0610	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				
0620	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	20.000 HR				
0630	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	50.000 HR				
0640	637.071 DUST CONTROL	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017576.00

PROJECT(S): BR-1757(600)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0650	639.18 FIELD OFFICE TYPE A	1.000 EA				
0660	652.312 TYPE III BARRICADE	4.000 EA				
0670	652.33 DRUM	12.000 EA				
0680	652.34 CONE	12.000 EA				
0690	652.35 CONSTRUCTION SIGNS	774.000 SF				
0700	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0710	652.38 FLAGGER	50.000 HR				
0720	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0730	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					