

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017999.00

PROJECT(S): STP-1799(600)X  
STP-1799(900)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 HIGHWAY ITEMS

0010	202.203 PAVEMENT BUTT JOINTS	2510.000 SY				
0020	304.103 AGGREGATE SUBBASE - GRAVEL (TRUCK MEASURE)	280.000 CY				
0030	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	210.000 T				
0040	403.210 HOT MIX ASPHALT 9.5 MM	5820.000 T				
0050	403.212 HOT MIX ASPHALT 4.75 MM - SHIM	1740.000 T				
0060	403.213 HOT MIX ASPHALT 12.5 MM BASE	60.000 T				
0070	409.15 BITUMINOUS TACK COAT - APPLIED	3280.000 G				
0080	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	160.000 CY				
0090	603.45 48 INCH REINFORCED CONCRETE PIPE CLASS IV	100.000 LF				
0100	606.36 GUARDRAIL REMOVED AND RESET	200.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017999.00

PROJECT(S): STP-1799(600)X  
STP-1799(900)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	606.362 GUARDRAIL ADJUSTED	200.000 LF				
0120	610.08 PLAIN RIPRAP	20.000 CY				
0130	615.07 LOAM	30.000 CY				
0140	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	110.000 UN				
0150	619.1201 MULCH - PLAN QUANTITY	110.000 UN				
0160	620.58 EROSION CONTROL GEOTEXTILE	50.000 SY				
0170	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0180	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR				
0190	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	100.000 HR				
0200	631.14 GRADER (INCLUDING OPERATOR)	40.000 HR				
0210	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	200.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 017999.00

PROJECT(S): STP-1799(600)X  
STP-1799(900)X

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR				
0230	652.312 TYPE III BARRICADE	10.000 EA				
0240	652.34 CONE	80.000 EA				
0250	652.35 CONSTRUCTION SIGNS	1221.000 SF				
0260	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	55.000 CD				
0270	652.38 FLAGGER	1290.000 HR				
0280	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0290	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					