

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 018007.00

PROJECT(S): STP-1800(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 HIGHWAY ITEMS						
0010	202.202 REMOVING PAVEMENT SURFACE	131350.000 SY				
0020	202.203 PAVEMENT BUTT JOINTS	5590.000 SY				
0030	203.242 DIRTY BORROW	180.000 CY				
0040	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	13900.000 T				
0050	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	680.000 T				
0060	409.15 BITUMINOUS TACK COAT - APPLIED	6900.000 G				
0070	411.09 UNTREATED AGGREGATE SURFACE COURSE	50.000 CY				
0080	604.161 ALTERING CATCH BASIN	43.000 EA				
0090	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	10.000 EA				
0100	604.182 CLEAN EXISTING CATCH BASIN AND MANHOLE	71.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 018007.00

PROJECT(S): STP-1800(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	606.24 GUARDRAIL TYPE 3D - SINGLE RAIL	1840.000 LF				
0120	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	20.000 EA				
0130	606.754 WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	4.000 EA				
0140	606.79 GUARDRAIL 350 FLARED TERMINAL	10.000 EA				
0150	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	40.000 UN				
0160	619.12 MULCH	40.000 UN				
0170	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	54300.000 LF				
0180	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	7070.000 SF				
0190	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0200	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR				
0210	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 018007.00

PROJECT(S): STP-1800(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR				
0230	639.19 FIELD OFFICE TYPE B	1.000 EA				
0240	643.86 TRAFFIC SIGNAL LOOP DETECTORS	80.000 EA				
0250	652.312 TYPE III BARRICADE	4.000 EA				
0260	652.33 DRUM	100.000 EA				
0270	652.34 CONE	300.000 EA				
0280	652.35 CONSTRUCTION SIGNS	1640.000 SF				
0290	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	75.000 CD				
0300	652.38 FLAGGER	2000.000 HR				
0310	652.381 TRAFFIC OFFICER	100.000 HR				
0320	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 018007.00

PROJECT(S): STP-1800(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0340	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	3200.000 SY				
0350	659.10 MOBILIZATION	LUMP	LUMP			
SECTION 0001 TOTAL						.

SECTION 0002 UTILITY ITEMS

0360	823.011 GATE VALVE BOX, INSTALL ONLY	EA	8.000			
0370	823.332 GATE VALVE BOX, ADJUST TO GRADE	EA	90.000			
SECTION 0002 TOTAL						.

SECTION 0003 TRAFFIC ITEMS

0380	643.83 VIDEO DETECTION SYSTEM AT WILLOWDALE RD. / ENTERPRISE DR.	LUMP	LUMP			
0390	643.83 VIDEO DETECTION SYSTEM GREENACRES LANE / HILLCREST AVE.	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 018007.00

PROJECT(S): STP-1800(700)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0400	643.83 VIDEO DETECTION SYSTEM HANNAFORD DR.	LUMP	LUMP			
0410	643.83 VIDEO DETECTION SYSTEM MUNICIPAL CAMPUS / WARD AVE.	LUMP	LUMP			
0420	643.83 VIDEO DETECTION SYSTEM PORTLAND FARMS RD.	LUMP	LUMP			
	SECTION 0003 TOTAL					
	TOTAL BID					