



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE
04333-0016

PAUL R. LEPAGE
GOVERNOR

January 21, 2011
Subject: **Falmouth**
Federal Project No: AC-BR-1709(203)X
State Pin No: 017092.03
Amendment No. 1

Dear Sir/Ms:

Make the following changes to the Bid Documents:

In the Bid Book (page 45) SPECIAL PROVISION, SECTION 502, STRUCTURAL CONCRETE CULVERT INVERT LINING" make the following **CHANGES** in pen and ink in the paragraph that begins "Materials";

In the first sentence, **DELETE** the words "modified Class LP" and **REPLACE** with "**Class A**".

In the second sentence, **DELETE** the words "**include a chemical accelerator and shall**".

In the Bid Book, after page 59, **ADD** the attached "SPECIAL PROVISIONS, SECTION 621, LANDSCAPE", 1 page dated October 13, 2010.

The following questions have been received:

Question: Special Provision 502, page 41 of the bid book specifies Class A. QC method C for the structural concrete while page 45 specifies class LP mix with accelerator. Please clarify.

Response: Class A or Shotcrete shall be used instead of LP modified. Please see the above pen and ink change.

Question: I could not find a plant list for item 621.197, Med. Deciduous Tree. Please point out the page in the bid book or provide list.

Response: Please see the above Special Provision 621.

Consider this information prior to submitting your bid on February 2, 2011.

Sincerely,

Scott Bickford
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

SPECIAL PROVISIONS
SECTION 621
LANDSCAPE

(Plant Species Specification and Quantities List)

The following list of items provides the estimated quantities for use on this project. The scientific name of the plant material is provided along with the common name in parenthesis.

The contractor shall follow MDOT Standard Specifications Rev. December, 2002 for landscape materials and installation procedures (sec. 621).

The MDOT Landscape Architect or his designee will be available to inspect plant materials and stake the location of plant materials at the time of planting.

In accordance with Section 104.5.9, a separate Performance Bond will not be required for the Landscape portion of this contract. No maintenance bond will be required, however a two-year warrantee will be included incidental to the planting.

PLANT MATERIALS

ITEM NO	Description	Unit	Quantity	Total
621.197	Med. Dec.Trees Group A 1 ¾" – 2" cal B&B	Ea.		6
	Acer rubrum (Red Maple)		3	
	Acer saccharum (Sugar Maple)		3	

*

*

*