



Paul R. LePage
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

March 9, 2012
Subject: **Crushing Services –
Regions 2, 3 & 4**
State PIN: N/A
Amendment No. 1

David Bernhardt
COMMISSIONER


Dear Sir/Ms:

Make the following changes to the Bid Documents:

In the Bid Book (pages 23 & 24), **REMOVE** the first two pages of “APPENDIX A, SPECIAL PROVISION, SPECIFICATIONS OF WORK TO BE PERFORMED”, 2 pages total (also labeled Page 1 of 6 and & Page 2 of 6) dated February 23, 2012 and **REPLACE** with the attached new “APPENDIX A, SPECIAL PROVISION, SPECIFICATIONS OF WORK TO BE PERFORMED”, pages 1 & 2 dated March 7, 2012”.

Consider these changes and information prior to submitting your bid on March 21, 2012.

Sincerely,

for


George Macdougall
Acting Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

APPENDIX A
 SPECIAL PROVISION
SPECIFICATIONS OF WORK TO BE PERFORMED

SCHEDULE OF ITEMS

Contractor _____

Bids are requested for multiple Regions in the state. A Bidder is not required to bid all Regions, and may bid on one or more Region(s).

Item Description	Approximate Quantity & Units	Unit Price \$/CY	Bid Amount \$
Region 2 Sidney Maintenance Lot	7,250 CY		
Region 3 Dallas Plt Maintenance Lot	6,000 CY		
Region 4 Plymouth Maintenance Lot	10,300 CY		

Description The Contractor shall crush the Hot Bituminous Pavement and other similar material in the stockpiles designated by the Department so that the maximum aggregate size of the finished product does not exceed 3/4". Contractor shall construct stockpiles such that equipment is not driven onto freshly crushed pile. The Department may sample for verification and approval.

The following stockpiles are to be crushed. The estimates have been given for informational purposes only. It will be the responsibility of the Contractor to verify the dimensions prior to beginning work.

Region	Approximate Quantity	Location	
Region 2	7,250 CY	Sidney Maintenance Lot	109 Lyons Road, east on Lyons Road from I95 exit
Region 3	6,000 CY	Dallas Plt Maintenance Lot	Rte. 16, 2 miles east on Rte. 16 out of Rangely
Region 4	10,300 CY	Plymouth Maintenance Lot	On Rte. 7, at Jct of I-95 & 7

Contract Time The contractor will be allowed to commence work on or after the following dates:

- Region 2 May 1, 2012**
- Region 3 June 6, 2012**
- Region 4 June 18, 2012**

The completion date for crushing services is as follows:

- Region 2 May 21, 2012**
- Region 3 June 20, 2012**
- Region 4 July 3, 2012**

Equipment Jaw crusher and/or cone crusher, screen, minimum 25,000# loader with 3 CY bucket or larger, minimum 50,000# excavator with 2 CY bucket or larger, minimum capacity of 1000 cy per day.