



Paul R. LePage  
GOVERNOR

STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

March 23, 2012  
Subject: **Drainage Replacement**  
Location: **Burnham**  
State Pin No: **N/A**  
**Amendment No. 2**

David Bernhardt  
COMMISSIONER

Dear Sir/Ms:


The following question has been received:

**Question:** What is the depth of pavement to be placed in the trenches once the concrete is removed and the new culverts and required gravel is installed? Is the Contractor to install a total of 10 inches of pavement?

**Response:** 4 inches total HMA, not to exceed 3 inches in a single lift as stated in the construction notes.

Consider this information prior to submitting your bid on March 28, 2012.

Sincerely,

  
George Macdougall  
Acting Contracts & Specifications Engineer



IMPROVE OR RECYCLE FIRST