



STATE OF MAINE  
 DEPARTMENT OF TRANSPORTATION  
 16 STATE HOUSE STATION  
 AUGUSTA, MAINE 04333-0016

Paul R. LePage  
 GOVERNOR

David Bernhardt  
 COMMISSIONER

May 31, 2013  
 Subject: **Deer Isle & Sedgwick**  
 Federal Project No: HP-1006(210)  
 State WIN: 010062.10  
**Amendment No. 2**

Dear Sir/Ms:

Make the following changes to the Bid Document:

In the Bid Book, after page 98, **REMOVE** "SPECIAL PROVISION, SECTION 536, Tensioning Existing Stay Cables" 2 pages dated May 24, 2013 (added in Amendment #1) and **REPLACE** with the attached new "SPECIAL PROVISION, SECTION 504, Tensioning Existing Stay Cables" 2 pages dated May 24, 2013.

In the Plans, Sheet Number 2 of 19, **DELETE** the following items added in Amendment #1 to the "ESTIMATED QUANTITIES" in pen and ink;


ITEM NO.	DESCRIPTION	QUANTITY	UNIT
"536.30	Stiffening Girder Bearing-Bushing Replacement	1	LS
536.301	Shim Keeper Plate Assembly	80	EA"

**ADD** the following items to the "ESTIMATED QUANTITIES" in pen and ink;

ITEM NO.	DESCRIPTION	QUANTITY	UNIT
<b>"504.691</b>	<b>Tensioning Existing Stay Cables</b>	<b>1</b>	<b>LS</b>
<b>504.674</b>	<b>Shim Keeper Plate Assembly</b>	<b>80</b>	<b>EA"</b>

Consider these changes information prior to submitting your bid on June 5, 2013.

Sincerely,

*for*   
 George M. A. Macdougall P.E.  
 Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER

**Town: Deer Isle**  
**Project: HP-1006(210)**  
**WIN: 10062.10**  
**Date: May 24, 2013**

**SPECIAL PROVISION**  
**SECTION 504**  
**Tensioning Existing Stay Cables**

Description:

The work shall consist of tensioning stay cables in the manner described and at locations as listed in the Contract Documents and/or as directed by the Resident.

The work shall also consist of furnishing and installing shim keeper plate assemblies at locations as listed in the Contract Documents and/or as directed by the Resident. One shim keeper plate assembly shall consist of two steel plates and two 5/8" diameter bolts with nuts and washers, as shown on the Contract Drawings.

This work shall be done in conformance with the Maine DOT Standard Specifications, Sections 504 – *Structural Steel* and 524– *Temporary Structural Supports*, except as modified by the Contract Documents. It is the intent and purpose of this special provision to cover and include all tools, equipment, materials, supplies, and labor necessary to complete the work described herein. Any incidental equipment, materials, supplies, or labor, such as the erection of false work to gain access to a removal/repair location, not specifically mentioned herein, which may be found necessary to complete the work in a substantial manner, shall be incidental to the respective payment item.

Submittals:

All the requirements of the Standard Specifications, Section 504 - *Structural Steel* shall be met, except as modified by these Contract Documents.

Materials and Workmanship:

Materials shall meet the requirements specified in Division 700 – *Materials* of the Standard Specifications, except where modified by these Contract Documents.

New bar bolts shall be ASTM A490; new nuts shall be ASTM A563; and new washers shall be ASTM F436.

Cleaning and painting material and workmanship shall meet the requirements of Section 506 *Field and Touch-up Painting* of these Special Provisions.

Method of Measurement:

Tensioning Existing Stay Cables shall not be measured for payment.

Shim Keeper Plate Assemblies shall be measured by the number, EACH, of assemblies furnished, installed and accepted by the Resident. No additional measurement shall be made for field fitup of new shim keeper plates.

**Town: Deer Isle**  
**Project: HP-1006(210)**  
**WIN: 10062.10**  
**Date: May 24, 2013**

Basis of Payment:

Tensioning Existing Stay Cables shall be paid for at the Contract Lump Sum Price Bid, under Item 504.691, which price shall include full compensation for all materials, transportation, tools, equipment, and labor required to perform the work as specified herein, as shown on the Contract Drawings, and/or as directed by the Resident.

Shim Keeper Plate Assemblies shall be paid for at the Contract Unit Price Bid, EACH, under Item 504.674 which price shall include full compensation for all materials, transportation, tools, equipment, and labor required to perform the work as specified herein, as shown on the Contract Drawings, and/or as directed by the Resident.

<u>Pay Item</u>	<u>Pay Unit</u>
504.691 Tensioning Existing Stay Cables	LS
504.674 Shim Keeper Plate Assembly	EA