



Paul R. LePage
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

April 18, 2013
Subject: **Brewer**
Federal Project No: STP-1183(500)X
State WIN: 011835.00
Amendment No. 2

David Bernhardt
COMMISSIONER

Dear Sir/Ms:

Make the following changes to the Bid Document:

In the Bid Book (pages 17 thru 20) **REMOVE** the "SCHEDULE OF ITEMS" 4 pages dated 130320 and **REPLACE** with the attached new "SCHEDULE OF ITEMS" 4 pages dated 130418.

In the Bid Book (page 41), "SPECIAL PROVISION, SECTION 104, Utilities" SUBSURFACE, Summary, Brewer Environmental Services Dept., **CHANGE** the "Estimated Working Days" from "1" day to read "**2**", and **CHANGE** the "Total:" from "2" to read "**3**". Make these changes in pen and ink.

In the Bid Book (page 42), "SPECIAL PROVISION, SECTION 104, Utilities" make the following **CHANGES** in pen and ink;

1. Under Brewer Environmental Services Department (ESD), **DELETE** the first two sentences in the first paragraph.
2. In the 2nd paragraph, last sentence, **DELETE** the word "contractor" and **REPLACE** with "City of Brewer".

In the Plans, Sheet Number C-02 of 8, Trail End Plan, and Trail Plan details, **DELETE** the notes that begin, "Detectable Warning Pavers to meet ADA.....determined by owner." Make this change in pen and ink.

In the Plans, Sheet Number C-01 of 8, Trail Plan details, **DELETE** following note: "Remove and replace existing storm drain vault hatch." Make this change in pen and ink.

The following questions have been received:

Question: It appears the vault hatch has just recently been replaced. Has this been taken into consideration and does it still need to be done?

Response: It does not need to be done. Item 845.20 Utility Access Door is deleted. Please see the attached Schedule of Items.

Question: Will it be necessary to replace the Access Door? I understand it was replaced within City of Brewers Hardy Street Project.



PRINTED ON RECYCLED PAPER

Response: See response to question above.

Question: Can you provide a cross section where the trail crosses the concrete vault at approx.. 2+68 or please explain the intent of how the trail will intersect the existing concrete vault at this station. Will there be fill on the vault, pavement on the vault, or should we match into the vault?

Response: The intent is to match into the vault. The profile illustrates that the trail grade matches existing at that location.

Question: Item 622.11 Transplanting Tree, would the MDOT allow for new 3" caliper of similar trees in lieu of transplanting? We are considering the time of year this would be done and the larger size of the trees to be transplanted.

Response: No

Question: Item 625.20 Relocation of Water Hand Pump, is this pump on a live line? If so, where is the line shutoff? Does it require any testing of chlorination?

Response: The hand pump (frost-proof hydrant) is connected to a underground pressurized line. The shutoff is in the sewer pump station near sta. 3+25. Chlorination and testing are not required.

Consider these changes and information prior to submitting your bid on April 24, 2013.

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer

for

SCHEDULE OF ITEMS

CONTRACT ID: 011835.00

PROJECT(S): STP-1183(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	202.15 REMOVING MANHOLE OR CATCH BASIN	1.000 EA				
0020	202.211 DECORATIVE BOULDER RELOCATION	20.000 EA				
0030	203.20 COMMON EXCAVATION	1150.000 CY				
0040	203.21 ROCK EXCAVATION	100.000 CY				
0050	203.26 GRAVEL BORROW	100.000 CY				
0060	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	100.000 CY				
0070	304.09 AGGREGATE BASE COURSE - CRUSHED	1450.000 CY				
0080	403.210 HOT MIX ASPHALT 9.5 MM	220.000 T				
0090	403.213 HOT MIX ASPHALT 12.5 MM BASE	300.000 T				
0100	603.179 18 INCH CULVERT PIPE OPTION III	10.000 LF				

SCHEDULE OF ITEMS

CONTRACT ID: 011835.00

PROJECT(S): STP-1183(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	8.000 EA				
0120	605.09 6 INCH UNDERDRAIN TYPE B	150.000 LF				
0130	608.26 CURB RAMP DETECTABLE WARNING FIELD	18.000 SF				
0140	610.08 PLAIN RIPRAP	10.000 CY				
0150	610.60 BARRIER BOULDERS	45.000 EA				
0160	615.07 LOAM	200.000 CY				
0170	618.13 SEEDING METHOD NUMBER 1	1.000 UN				
0180	620.58 EROSION CONTROL GEOTEXTILE	320.000 SY				
0190	622.11 TRANSPLANTING TREE	12.000 EA				
0200	625.20 RELOCATION OF HAND WATER PUMP	LUMP	LUMP			
0210	629.05 HAND LABOR, STRAIGHT TIME	8.000 HR				

SCHEDULE OF ITEMS

CONTRACT ID: 011835.00

PROJECT(S): STP-1183(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	8.000 HR				
0230	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	8.000 HR				
0240	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	8.000 HR				
0250	634.162 PARK LIGHTING SYSTEM	LUMP	LUMP			
0260	645.251 ROADSIDE GUIDE SIGNS	16.000 SF				
0270	652.312 TYPE III BARRICADE	6.000 EA				
0280	652.33 DRUM	6.000 EA				
0290	652.34 CONE	10.000 EA				
0300	652.35 CONSTRUCTION SIGNS	200.000 SF				
0310	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	90.000 CD				
0320	652.38 FLAGGER	40.000 HR				

SCHEDULE OF ITEMS

CONTRACT ID: 011835.00

PROJECT(S): STP-1183(500)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					