



Paul R. LePage
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

David Bernhardt
COMMISSIONER

May 24, 2013
Subject: **Poland**
Federal Project No: STP-1788(300)
State WIN: 017883.00
Amendment No. 2

Dear Sir/Ms:

The following question has been received:

Question: Is the pavement being removed within the cuts/fills required to be milled or reclaimed or can it be picked up by an excavator? Is the pavement the property of the Contractor?

Response: Pavement removed within the reconstruction area (Sta. 102+00 to 152+50) can be removed by any method the contractor desires. The pavement removed in this area will be the property of the contractor. Pavement outside of the reconstruction area (Sta. 100+30 to 102+00, and Sta. 152+00 to 158+00) shall be milled.

Consider this information prior to submitting your bid on May 29, 2013.

Sincerely,

George M. A. Macdougall P.E.
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER