



Paul R. LePage
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

April 25, 2014

Subject: **Islesboro Crew Quarters** COMMISSIONER David Bernhardt

Federal Project No: 018407.00

State 018407.00

Amendment No. 5

Dear Sir/Ms:

The following questions have been received:

Question: The Specification Section 066500: 2.1A calls for Boral Composites trim on the exterior. Sheet 4 & 5 refer to aluminum fascia covering (Coil Trim?). The elevations on sheet show a window trim and no door trim; sheet 5, Section "A" & "B" show no face trim at the windows. Please clarify.

Response: Composite trims are required on all new entry doors and windows to be installed. All perimeter gable and rake trims along with the all window build outs are to be covered with the Coil Stock.

Question: Sheet 3 ADA Bathroom, Grab bars are shown in the new ADA Bathroom. Are additional toilet accessories to be included? (Mirror, toilet paper dispenser, coat hooks, soap dispenser, paper towel dispenser, etc) Please advise.

Response: The only additional accessories that are to be included is a mirror above the sink, which will be submitted during the submittal process.

Question: Drawing 3, Bedroom Closet, Is there shelving to be supplied in the closet and if so what type and quantity?

Response: There is no shelving in the closet area(s), this will be done by the owner.

Question: Sheet 3, ADA Bathroom, there appears to be a vanity shown at the sink in the ADA bathroom. If so, what size, style and manufacturer?

Response: The vanity in the ADA bathroom will be submitted by the winning Contractor (s) during the submittal process.




PRINTED ON RECYCLED PAPER

Question: Reference Sheet 2; Is the 8 x 12 shed to be included in the project or just the foundation? What is the foundation and if the building is to be included, can we get some detail as to what is anticipated?

Response: The 8' x12' shed is to be included along with the foundation, siding colors by owner. The foundation will consist of (6) 24" round concrete pads. The shed style etc. will be submitted during the submittal process.

Consider this information prior to submitting your bid on April 30, 2014.

Sincerely,

A handwritten signature in blue ink that reads "George M. A. Macdougall". The signature is fluid and cursive, with the first letters of each word being capitalized and prominent.

George M. A. Macdougall P.E.
Contracts & Specifications Engineer