STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

April 25, 2014
Subject: Salt Storage Building
Location: Hancock
State Pin No: 020137.00
Amendment No. 1

Dear Sir/Ms:

The following questions have been received:

Question: Drawing sheet 5 of 14, upper right hand corner shows a slope of ¼" per foot for the grade at the front of the building. There is also a note that says to create a constant grade from the building to the existing drive entrance elevation which is approximately elv. 105.5 and 140 ft away at centerline. Does the ¼" per foot apply to just the 30 ft paved apron or is it just a minimum slope to be used? The slope difference between the finish slab and the existing access road is greater than 1/3" per foot.

Response: The ¼" per foot applies only to the 30' paved apron, then the gravel from this point will be graded to match the existing entrance elevation.

Question: Does any of the construction area get loam, seed, and mulch when completed?

Response: Please see in the Bid Book (page 29)"General Notes" line 4, "Loam and seeding and as well as backing up of any new pavement areas and any area disturbed during this particular project shall be the responsibility of the Contractor"

Consider this information prior to submitting your bid on April 30, 2014.

Sincerely,

George M. A. Macdougall P.E.
Contracts & Specifications Engineer