STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

July 25, 2014
Subject: **Albion**
State WIN: 021210.00
Amendment No. 3

Dear Sir/Ms:

Make the following change to the Bid Document:

In the Bid Book (page 32) **REMOVE** "SPECIAL PROVISION, SECTION 107, TIME" 1 page dated June 20, 2014 and **REPLACE** with the attached new "SPECIAL PROVISION, SECTION 107, TIME" 1 page dated July 24, 2014.

The following questions have been received:

Question: The depth of cut required to perform this work and the presence of traffic adjacent to the embankment necessitates a site-specific shoring design to comply with OSHA rules. Recent slope failure is obvious evidence of potential safety issues. Will the Department require submission of the shoring design for review?

Response: MaineDOT will not be required to review and approve shoring protection plan. The contractor will need an engineered plan with an engineer's stamp onsite at all times available for MaineDOT to review at any time.

Question: Seven days is not enough time to install a shoring system and perform the work safely. Would the Department consider extending the allowable work time?

Response: Please see the attached new Special Provision 107.

Consider this change and information prior to submitting your bid on July 30, 2014.

Sincerely,

George M. A. Macdougall P.E.
Contracts & Specifications Engineer

PRINTED ON RECYCLED PAPER

THE MAINE DEPARTMENT OF TRANSPORTATION IS AN AFFIRMATIVE ACTION - EQUAL OPPORTUNITY EMPLOYER
PHONE: (207) 624-3000 TTY: 888-516-9364 FAX: (207) 624-3001

Albion Route 202
Win 21210.00
Culvert End Resetting
July 24, 2014

SPECIAL PROVISION
SECTION 107
TIME
(Contract Time)

All work shall be completed by October 1st, 2014.

The contractor may begin work at any time after August 15th as long as the contract is awarded and Soil Erosion plan has been approved.

Once work begins, the contractor will have a 14 calendar day window to complete 100% of the project.

The contractor will be charged $500/day in liquidated damages for every day past the 14 calendar days allotted for the completion of the project.