



Paul R. LePage  
GOVERNOR

STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

David Bernhardt  
COMMISSIONER

July 8, 2015  
Subject: Hwy Reconstruction  
State WIN: 0191940.00  
Location: **Eastport**  
**Amendment No. 1**

Dear Sir/Ms:

The following question has been received:

**Question:** Will the DOT allow the use of 18" ADS Sanitite HP pipe as an alternate to the 18" RCP class III on the plans?

**Response:** According to the Department's cross pipe policy, this project will require the utilization of RCP

**REMOVE** page 51, "SPECIAL PROVISION SECTION 105" dated 6/24/15 and **REPLACE** with the attached revised "SPECIAL PROVISION SECTION 105", 1 page, dated 7/8/2015.

Consider this change and information prior to submitting your bid on **July 22, 2015**.

Sincerely,

  
George M. A. Macdougall P.E.  
Contracts & Specifications Engineer

PRINTED ON RECYCLED PAPER

**SPECIAL PROVISION  
SECTION 105  
General Scope of Work  
(Limitations of Operations)**

1. Lane closures shall be set up as stated in the Special Provision 652, Traffic Control Guidelines and as per MUTCD.
2. The Contractor's traffic control plan shall discuss/address ways to minimize impact to the traveling public.
3. All work schedule changes must be submitted for approval to the Department a minimum of 2 calendar days prior to the requested change.
4. The Contractor will be limited to one paving operation and one hand work operation at a time unless otherwise authorized by the Resident.
5. The Contractor shall stop all work and have all lanes open to traffic on the following dates:  
  
September 4, 2015 by 3:00 P.M. and shall not commence work until September 8, 2015 (Labor Day).  
  
May 27, 2016 by 3:00 P.M. and shall not commence work until May 31, 2016 (Memorial Day).  
  
July 1, 2016 by 12:00 P.M. and shall not commence work until July 5, 2016 (Independence Day).
6. Clearing consisting of trees larger than 3" in diameter shall not be done until after October 15<sup>th</sup>, 2015, and shall be completed prior to April 19<sup>th</sup>, 2016.
7. The embankment fill for the construction of the new alignment to be done by December 18<sup>th</sup>, 2015 or prior to frost penetrating the ground, whichever comes sooner.
8. The embankment fill is to be preloaded for three months prior to the placement of pavement.