



Paul R. LePage  
GOVERNOR

STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

David Bernhardt  
COMMISSIONER

March 28, 2016  
Subject: Full Depth Pavement,  
Milling/Overlay, Drainage & Safety  
Improvements  
State WIN: 018289.00 & 022574.00  
Location: **Sebec, Milo and Dover  
Foxcroft  
Amendment No. 2**

Dear Sir/Ms:

The following questions have been received:

Question: Item 606.358 modify is the post spacing 6'3" now or 12'6", steel post or wood post?

Response: The existing post spacing is 6'3" and the existing guardrail posts are steel.

Question: Are there existing end treatments(BCI, melts) on the project?

Response: The existing guardrail end treatments are BCT's which will be replaced with either Item 606.232 Guardrail Type 3C – Over 15' radius or Item 606.79 Guardrail 350 Flared Terminal.

Consider this change and information prior to submitting your bid on **March 30, 2016.**

Sincerely,

George M. A. Macdougall P.E.  
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER