STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

March 21, 2016
Milling/Overlay with Drainage Improvements
State WIN: 018641.00
Location: **Brewer**
Amendment No. 1

Dear Sir/Ms:

The following questions have been received:

Question: Would slipform Curb be an acceptable alternative to Curb type3?

Response: Concrete Slipform Curb will not be considered as an acceptable alternative to Item 609.31 Type 3 Curb. Areas where Item 609.16 Concrete Slipform Curb shall be utilized are identified in the Bid Documents.

Question: Item 604.262 CB type B5-C, is there an existing pipe that this structure will be outletted to? If so, what type & size pipe. Is the 6" UD to be connected to an existing pipe or just dead ended?

Response: Item 604.262 Catch Basin Type B5-C will outlet into the existing run of 6" underdrain type B at approximate station 27+00 right. Item 605.09 - 6" Underdrain Type B will be utilized to outlet and connect the proposed catch basin at station 26+80 right to the existing 6" underdrain type B.

Consider this change and information prior to submitting your bid on **March 30, 2016**.

Sincerely,

George M. A. Macdougall P.E.
Contracts & Specifications Engineer

PRINTED ON RECYCLED PAPER

THE MAINE DEPARTMENT OF TRANSPORTATION IS AN AFFIRMATIVE ACTION - EQUAL OPPORTUNITY EMPLOYER
PHONE: (207) 624-3000 TTY USERS CALL MAINE RELAY 711 FAX: (207) 624-3001