




MAIN STREET (NEW YORK TO MEMORY) WATER MAIN REPLACEMENT SOUTH PORTLAND, MAINE



**Portland Water District
Asset Management & Planning Department**

February 19, 2016

SR 330277



EXISTING AND TEMPORARY MAINS
1" = 40'




PROPOSED MAINS
1" = 40'

- NOTES**
1. CONTRACTOR SHALL DISPOSE OF ALL EXCAVATED PIPING AND APPURTENANCES.
 2. ALL MAINS AND SERVICES SHALL BE INSTALLED WITH 5.5' OF COVER MEASURED FROM PROPOSED ROAD GRADE UNLESS OTHERWISE APPROVED BY A PWD REPRESENTATIVE.
 3. THE PORTLAND WATER DISTRICT WILL NOTIFY CUSTOMERS FOR ALL WORK INVOLVING TEMPORARY SHUT DOWN OF SERVICE. CUSTOMERS MUST RECEIVE AT LEAST 48 HOURS NOTIFICATION PRIOR TO ANY SHUT DOWN. THE DISTRICT MUST RECEIVE NOTICE FROM THE CONTRACTOR OF THE SHUT DOWN AT LEAST 48 HOURS PRIOR TO CUSTOMER NOTIFICATION.
 4. ALL DUCTILE IRON PIPE AND FITTINGS SHALL BE POLY-WRAPPED PER SPECIFICATIONS.
 5. THE COST OF PROVIDING TEMPORARY WATER SERVICE TO THE BUILDINGS INDICATED ON THE PLAN SHALL BE AN INCIDENTAL COST FOR WHICH SEPARATE PAYMENT WILL NOT BE MADE. IF PROPERTIES REQUIRING A TEMPORARY WATER CONNECTION HAVE MALFUNCTIONING SILLCOCKS OR NO EXTERIOR PLUMBING, IT MAY BE NECESSARY TO EXCAVATE AND CONNECT INTO THE EXISTING SERVICE LINE BEHIND THE EXISTING SHUT-OFF VALVE TO PROVIDE TEMPORARY SERVICE.
 6. PROVIDE TEMPORARY MAIN CONNECTION TO HYDRANT USING LL BRASS OR 304 SS ADAPTER, 304 SS NPT TO HDPE TRANSITION, AND FLANGED HDPE PIPING TO BRING PIPING ELEVATION FROM HYDRANT PORT TO GRADE. PROVIDE PIPING SUPPORTS/BLOCKING AT FITTINGS. HDPE SHALL BE AWWA C906, SDR 11 WITH IPS FLANGE ADAPTERS AND DI BACKUP RINGS, DIMENSIONS PER AWWA C207. ALL PIPING AND FITTINGS SHALL BE NSF 61.
 7. PROVIDE FLANGED LL DOUBLE CHECK VALVE BACKFLOW DEVICE, SAME NOMINAL SIZE AS TEMP MAIN, AT EACH HYDRANT CONNECTED TO A TEMPORARY MAIN. PROVIDE FLANGED RESILIENT SEATED GATE VALVES FOR ISOLATION, AND PROVIDE UPSTREAM AND DOWNSTREAM TAPS. REMOVE BACKFLOW ONLY UPON OWNER'S REQUEST AND PROVIDE FLANGED HDPE REPLACEMENT SPOOL PIECE. HDPE SHALL BE AWWA C906, SDR 11 WITH IPS FLANGE ADAPTERS AND DI BACKUP RINGS. FLANGE DIMENSIONS PER AWWA C207. ALL PIPING AND FITTINGS SHALL BE NSF 61. PROVIDE DOCUMENTATION OF ANNUAL INSPECTION BY A PERSON CERTIFIED BY THE NEW ENGLAND WATER WORKS ASSOCIATION OR AMERICAN BACKFLOW PREVENTION ASSOCIATION.
 8. INSTALL 4" TEMPORARY FIRE DEPT CONNECTION (TYP.), 4" GATE VALVE, 90° ELBOW, RISER PIPE, 90° ELBOW, AND 4-1/2" NPT STEAMER PORT CONNECTION WITH CAP. ALL JOINTS TO BE RESTRAINED. STEAMER PORT, RISER AND TEE TO BE ANCHORED TO THE GROUND. OUTLET TO BE BETWEEN 1' AND 2' OFF THE GROUND.
 9. REMOVE ALL OLD PIPING NOT EXPLICITLY CALLED OUT FOR ABANDONMENT.
 10. TEMPORARY WATER SYSTEM SHALL ONLY BE ACTIVE BETWEEN APRIL 15TH AND OCTOBER 15TH. ALL WATER MAIN, EITHER EXISTING OR NEWLY INSTALLED, MUST BE ACTIVE BETWEEN OCTOBER 16TH AND APRIL 14TH. ALL 4" DIAMETER & LARGER TEMPORARY WATER LINES MUST BE BURIED WHEN CROSSING STREETS, DRIVEWAYS & SIDEWALKS.
 11. CONTRACTOR MUST ALLOW OWNER SUFFICIENT TIME TO TRANSFER WATER SERVICES FROM EXISTING WATER MAIN TO TEMPORARY WATER SERVICES INSTALLED BY CONTRACTOR AND TO TRANSFER SERVICE TO NEW WATER MAIN/SERVICE LINE UPON SUCCESSFUL TESTING OF SAMPLE FOR ABSENCE OF BACTERIA. THE CONTRACTOR SHALL NOT CLAIM ANY DELAY-RELATED COSTS OR TIME RELATED TO THIS WORK.
 12. REPLACE ALL SERVICES TO BE RENEWED FROM MAIN TO STREET LINE WITH 1" COPPER PIPING, UNLESS CALLED OUT TO BE REPLACED DIFFERENTLY.
 13. SIDEWALKS MUST REMAIN OPEN AT ALL TIMES OR REASONABLE DETOURS PROVIDED.
 14. LOCATIONS OF UTILITIES OTHER THAN WATER ARE APPROXIMATE, AND NOT ALL UTILITIES ARE SHOWN. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING, SUPPORTING AND PROTECTING ALL UTILITIES DURING INSTALLATION OF THE WATER MAIN.
 15. TEMPORARY WATER (INCLUDING SERVICES) SHALL BE ACTIVE FOR PHASE I AS SHOWN ON THE DRAWINGS BEFORE EXISTING WATER MAIN IS TAKEN OUT OF SERVICE. NEW MAIN SHALL BE PRESSURE/LEAK TESTED, DISINFECTED AND HAVE A SUCCESSFUL TESTING SAMPLE FOR ABSENCE OF BACTERIA BEFORE PHASE II MAY COMMENCE. LAYOUT OF TEMPORARY WATER (INCLUDING SERVICES) FOR PHASE II CAN OCCUR CONCURRENTLY WITH PHASE I WATER MAIN REPLACEMENT WORK. A SIMILAR SCHEDULE IS REQUIRED FOR PHASE III.
 16. THERE IS A CONCRETE SLAB UNDER THE PAVEMENT ON MAIN STREET. THE CONCRETE REMOVED WILL NOT BE REPLACED.

- LEGEND**
- EXISTING WATER MAIN
 - - - - - PROPOSED WATER MAIN
 - - - - - TEMPORARY WATER MAIN
 - - - - - PROPOSED/RENEWED SERVICE
 - - - - - RECONNECT SERVICE

PROJECT:
330277

**MAIN STREET
(NEW YORK TO MEMORY)
WATER MAIN REPLACEMENT
SOUTH PORTLAND, ME**




DRAWN BY:
MAM

DESIGN BY:
WEP


CHECKED BY:
WEP

DATE:
02/23/2016

Portland Water District
ASSET MANAGEMENT AND PLANNING DEPARTMENT
225 DOUGLASS STREET, PORTLAND ME 04104
(207) 774-5961 • WWW.PWD.ORG



EXISTING AND TEMPORARY MAINS
1" = 40'



PROPOSED MAINS
1" = 40'


- NOTES**
1. CONTRACTOR SHALL DISPOSE OF ALL EXCAVATED PIPING AND APPURTENANCES.
 2. ALL MAINS AND SERVICES SHALL BE INSTALLED WITH 5.5' OF COVER MEASURED FROM PROPOSED ROAD GRADE UNLESS OTHERWISE APPROVED BY A PWD REPRESENTATIVE.
 3. THE PORTLAND WATER DISTRICT WILL NOTIFY CUSTOMERS FOR ALL WORK INVOLVING TEMPORARY SHUT DOWN OF SERVICE. CUSTOMERS MUST RECEIVE AT LEAST 48 HOURS NOTIFICATION PRIOR TO ANY SHUT DOWN. THE DISTRICT MUST RECEIVE NOTICE FROM THE CONTRACTOR OF THE SHUT DOWN AT LEAST 48 HOURS PRIOR TO CUSTOMER NOTIFICATION.
 4. ALL DUCTILE IRON PIPE AND FITTINGS SHALL BE POLY-WRAPPED PER SPECIFICATIONS.
 5. THE COST OF PROVIDING TEMPORARY WATER SERVICE TO THE BUILDINGS INDICATED ON THE PLAN SHALL BE AN INCIDENTAL COST FOR WHICH SEPARATE PAYMENT WILL NOT BE MADE. IF PROPERTIES REQUIRING A TEMPORARY WATER CONNECTION HAVE MALFUNCTIONING SILLCOCKS OR NO EXTERIOR PLUMBING, IT MAY BE NECESSARY TO EXCAVATE AND CONNECT INTO THE EXISTING SERVICE LINE BEHIND THE EXISTING SHUT-OFF VALVE TO PROVIDE TEMPORARY SERVICE.
 6. PROVIDE TEMPORARY MAIN CONNECTION TO HYDRANT USING LL BRASS OR 304 SS ADAPTER, 304 SS NPT TO HDPE TRANSITION, AND FLANGED HDPE PIPING TO BRING PIPING ELEVATION FROM HYDRANT PORT TO GRADE. PROVIDE PIPING SUPPORTS/BLOCKING AT FITTINGS. HDPE SHALL BE AWWA C906, SDR 11 WITH IPS FLANGE ADAPTERS AND DI BACKUP RINGS, DIMENSIONS PER AWWA C207. ALL PIPING AND FITTINGS SHALL BE NSF 61.
 7. PROVIDE FLANGED LL DOUBLE CHECK VALVE BACKFLOW DEVICE, SAME NOMINAL SIZE AS TEMP MAIN, AT EACH HYDRANT CONNECTED TO A TEMPORARY MAIN. PROVIDE FLANGED RESILIENT SEATED GATE VALVES FOR ISOLATION, AND PROVIDE UPSTREAM AND DOWNSTREAM TAPS. REMOVE BACKFLOW ONLY UPON OWNER'S REQUEST AND PROVIDE FLANGED HDPE REPLACEMENT SPOOL PIECE. HDPE SHALL BE AWWA C906, SDR 11 WITH IPS FLANGE ADAPTERS AND DI BACKUP RINGS. FLANGE DIMENSIONS PER AWWA C207. ALL PIPING AND FITTINGS SHALL BE NSF 61. PROVIDE DOCUMENTATION OF ANNUAL INSPECTION BY A PERSON CERTIFIED BY THE NEW ENGLAND WATER WORKS ASSOCIATION OR AMERICAN BACKFLOW PREVENTION ASSOCIATION.
 8. INSTALL 4" TEMPORARY FIRE DEPT CONNECTION (TYP.), 4" GATE VALVE, 90° ELBOW, RISER PIPE, 90° ELBOW, AND 4-1/2" NPT STEAMER PORT CONNECTION WITH CAP. ALL JOINTS TO BE RESTRAINED. STEAMER PORT, RISER AND TEE TO BE ANCHORED TO THE GROUND. OUTLET TO BE BETWEEN 1' AND 2' OFF THE GROUND.
 9. REMOVE ALL OLD PIPING NOT EXPLICITLY CALLED OUT FOR ABANDONMENT.
 10. TEMPORARY WATER SYSTEM SHALL ONLY BE ACTIVE BETWEEN APRIL 15TH AND OCTOBER 15TH. ALL WATER MAIN, EITHER EXISTING OR NEWLY INSTALLED, MUST BE ACTIVE BETWEEN OCTOBER 16TH AND APRIL 14TH. ALL 4" DIAMETER & LARGER TEMPORARY WATER LINES MUST BE BURIED WHEN CROSSING STREETS, DRIVEWAYS & SIDEWALKS.
 11. CONTRACTOR MUST ALLOW OWNER SUFFICIENT TIME TO TRANSFER WATER SERVICES FROM EXISTING WATER MAIN TO TEMPORARY WATER SERVICES INSTALLED BY CONTRACTOR AND TO TRANSFER SERVICE TO NEW WATER MAIN/SERVICE LINE UPON SUCCESSFUL TESTING OF SAMPLE FOR ABSENCE OF BACTERIA. THE CONTRACTOR SHALL NOT CLAIM ANY DELAY-RELATED COSTS OR TIME RELATED TO THIS WORK.
 12. REPLACE ALL SERVICES TO BE RENEWED FROM MAIN TO STREET LINE WITH 1" COPPER PIPING, UNLESS CALLED OUT TO BE REPLACED DIFFERENTLY.
 13. SIDEWALKS MUST REMAIN OPEN AT ALL TIMES OR REASONABLE DETOURS PROVIDED.
 14. LOCATIONS OF UTILITIES OTHER THAN WATER ARE APPROXIMATE, AND NOT ALL UTILITIES ARE SHOWN. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING, SUPPORTING AND PROTECTING ALL UTILITIES DURING INSTALLATION OF THE WATER MAIN.
 15. TEMPORARY WATER (INCLUDING SERVICES) SHALL BE ACTIVE FOR PHASE I AS SHOWN ON THE DRAWINGS BEFORE EXISTING WATER MAIN IS TAKEN OUT OF SERVICE. NEW MAIN SHALL BE PRESSURE/LEAK TESTED, DISINFECTED AND HAVE A SUCCESSFUL TESTING SAMPLE FOR ABSENCE OF BACTERIA BEFORE PHASE II MAY COMMENCE. LAYOUT OF TEMPORARY WATER (INCLUDING SERVICES) FOR PHASE II CAN OCCUR CONCURRENTLY WITH PHASE I WATER MAIN REPLACEMENT WORK. A SIMILAR SCHEDULE IS REQUIRED FOR PHASE III.
 16. THERE IS A CONCRETE SLAB UNDER THE PAVEMENT ON MAIN STREET. THE CONCRETE REMOVED WILL NOT BE REPLACED.

LEGEND

- EXISTING WATER MAIN
- PROPOSED WATER MAIN
- TEMPORARY WATER MAIN
- PROPOSED/RENEWED SERVICE
- RECONNECT SERVICE

PROJECT:
330277

**MAIN STREET
(NEW YORK TO MEMORY)
WATER MAIN REPLACEMENT
SOUTH PORTLAND, ME**




DRAWN BY:
MAM


DESIGN BY:
WEP

CHECKED BY:
WEP


DATE:
02/23/2016

Portland Water District
ASSET MANAGEMENT AND PLANNING DEPARTMENT
225 DOUGLASS STREET, PORTLAND ME 04104
(207) 774-5961 • WWW.PWD.ORG





EXISTING AND TEMPORARY MAINS
1" = 40'



PROPOSED MAINS
1" = 40'

- NOTES**
1. CONTRACTOR SHALL DISPOSE OF ALL EXCAVATED PIPING AND APPURTENANCES.
 2. ALL MAINS AND SERVICES SHALL BE INSTALLED WITH 5.5' OF COVER MEASURED FROM PROPOSED ROAD GRADE UNLESS OTHERWISE APPROVED BY A PWD REPRESENTATIVE.
 3. THE PORTLAND WATER DISTRICT WILL NOTIFY CUSTOMERS FOR ALL WORK INVOLVING TEMPORARY SHUT DOWN OF SERVICE. CUSTOMERS MUST RECEIVE AT LEAST 48 HOURS NOTIFICATION PRIOR TO ANY SHUT DOWN. THE DISTRICT MUST RECEIVE NOTICE FROM THE CONTRACTOR OF THE SHUT DOWN AT LEAST 48 HOURS PRIOR TO CUSTOMER NOTIFICATION.
 4. ALL DUCTILE IRON PIPE AND FITTINGS SHALL BE POLY-WRAPPED PER SPECIFICATIONS.
 5. THE COST OF PROVIDING TEMPORARY WATER SERVICE TO THE BUILDINGS INDICATED ON THE PLAN SHALL BE AN INCIDENTAL COST FOR WHICH SEPARATE PAYMENT WILL NOT BE MADE. IF PROPERTIES REQUIRING A TEMPORARY WATER CONNECTION HAVE MALFUNCTIONING SILLCOCKS OR NO EXTERIOR PLUMBING, IT MAY BE NECESSARY TO EXCAVATE AND CONNECT INTO THE EXISTING SERVICE LINE BEHIND THE EXISTING SHUT-OFF VALVE TO PROVIDE TEMPORARY SERVICE.
 6. PROVIDE TEMPORARY MAIN CONNECTION TO HYDRANT USING LL BRASS OR 304 SS ADAPTER, 304 SS NPT TO HDPE TRANSITION, AND FLANGED HDPE PIPING TO BRING PIPING ELEVATION FROM HYDRANT PORT TO GRADE. PROVIDE PIPING SUPPORTS/BLOCKING AT FITTINGS. HDPE SHALL BE AWWA C906, SDR 11 WITH IPS FLANGE ADAPTERS AND DI BACKUP RINGS, DIMENSIONS PER AWWA C207. ALL PIPING AND FITTINGS SHALL BE NSF 61.
 7. PROVIDE FLANGED LL DOUBLE CHECK VALVE BACKFLOW DEVICE, SAME NOMINAL SIZE AS TEMP MAIN, AT EACH HYDRANT CONNECTED TO A TEMPORARY MAIN. PROVIDE FLANGED RESILIENT SEATED GATE VALVES FOR ISOLATION, AND PROVIDE UPSTREAM AND DOWNSTREAM TAPS. REMOVE BACKFLOW ONLY UPON OWNER'S REQUEST AND PROVIDE FLANGED HDPE REPLACEMENT SPOOL PIECE. HDPE SHALL BE AWWA C906, SDR 11 WITH IPS FLANGE ADAPTERS AND DI BACKUP RINGS. FLANGE DIMENSIONS PER AWWA C207. ALL PIPING AND FITTINGS SHALL BE NSF 61. PROVIDE DOCUMENTATION OF ANNUAL INSPECTION BY A PERSON CERTIFIED BY THE NEW ENGLAND WATER WORKS ASSOCIATION OR AMERICAN BACKFLOW PREVENTION ASSOCIATION.
 8. INSTALL 4" TEMPORARY FIRE DEPT CONNECTION (TYP.), 4" GATE VALVE, 90° ELBOW, RISER PIPE, 90° ELBOW, AND 4-1/2" NPT STEAMER PORT CONNECTION WITH CAP. ALL JOINTS TO BE RESTRAINED. STEAMER PORT, RISER AND TEE TO BE ANCHORED TO THE GROUND. OUTLET TO BE BETWEEN 1' AND 2' OFF THE GROUND.
 9. REMOVE ALL OLD PIPING NOT EXPLICITLY CALLED OUT FOR ABANDONMENT.
 10. TEMPORARY WATER SYSTEM SHALL ONLY BE ACTIVE BETWEEN APRIL 15TH AND OCTOBER 15TH. ALL WATER MAIN, EITHER EXISTING OR NEWLY INSTALLED, MUST BE ACTIVE BETWEEN OCTOBER 16TH AND APRIL 14TH. ALL 4" DIAMETER & LARGER TEMPORARY WATER LINES MUST BE BURIED WHEN CROSSING STREETS, DRIVEWAYS & SIDEWALKS.
 11. CONTRACTOR MUST ALLOW OWNER SUFFICIENT TIME TO TRANSFER WATER SERVICES FROM EXISTING WATER MAIN TO TEMPORARY WATER SERVICES INSTALLED BY CONTRACTOR AND TO TRANSFER SERVICE TO NEW WATER MAIN/SERVICE LINE UPON SUCCESSFUL TESTING OF SAMPLE FOR ABSENCE OF BACTERIA. THE CONTRACTOR SHALL NOT CLAIM ANY DELAY-RELATED COSTS OR TIME RELATED TO THIS WORK.
 12. REPLACE ALL SERVICES TO BE RENEWED FROM MAIN TO STREET LINE WITH 1" COPPER PIPING, UNLESS CALLED OUT TO BE REPLACED DIFFERENTLY.
 13. SIDEWALKS MUST REMAIN OPEN AT ALL TIMES OR REASONABLE DETOURS PROVIDED.
 14. LOCATIONS OF UTILITIES OTHER THAN WATER ARE APPROXIMATE, AND NOT ALL UTILITIES ARE SHOWN. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING, SUPPORTING AND PROTECTING ALL UTILITIES DURING INSTALLATION OF THE WATER MAIN.
 15. TEMPORARY WATER (INCLUDING SERVICES) SHALL BE ACTIVE FOR PHASE I AS SHOWN ON THE DRAWINGS BEFORE EXISTING WATER MAIN IS TAKEN OUT OF SERVICE. NEW MAIN SHALL BE PRESSURE/LEAK TESTED, DISINFECTED AND HAVE A SUCCESSFUL TESTING SAMPLE FOR ABSENCE OF BACTERIA BEFORE PHASE II MAY COMMENCE. LAYOUT OF TEMPORARY WATER (INCLUDING SERVICES) FOR PHASE II CAN OCCUR CONCURRENTLY WITH PHASE I WATER MAIN REPLACEMENT WORK. A SIMILAR SCHEDULE IS REQUIRED FOR PHASE III.
 16. THERE IS A CONCRETE SLAB UNDER THE PAVEMENT ON MAIN STREET. THE CONCRETE REMOVED WILL NOT BE REPLACED.

LEGEND

- EXISTING WATER MAIN
- PROPOSED WATER MAIN
- TEMPORARY WATER MAIN
- PROPOSED/RENEWED SERVICE
- RECONNECT SERVICE

PROJECT:

330277

**MAIN STREET
(NEW YORK TO MEMORY)
WATER MAIN REPLACEMENT
SOUTH PORTLAND, ME**

DRAWN BY:
MAM

DESIGN BY:
WEP

CHECKED BY:
WEP

DATE:
02/23/2016

Portland Water District

ASSET MANAGEMENT AND PLANNING DEPARTMENT
225 DOUGLASS STREET, PORTLAND ME 04104
(207) 774-5961 • WWW.PWD.ORG

SHEET:

3 OF 6



EXISTING AND TEMPORARY MAINS
1" = 100'

NOTES

1. CONTRACTOR SHALL DISPOSE OF ALL EXCAVATED PIPING AND APPURTENANCES.

2. ALL MAINS AND SERVICES SHALL BE INSTALLED WITH 5.5' OF COVER MEASURED FROM PROPOSED ROAD GRADE UNLESS OTHERWISE APPROVED BY A PWD REPRESENTATIVE.

3. THE PORTLAND WATER DISTRICT WILL NOTIFY CUSTOMERS FOR ALL WORK INVOLVING TEMPORARY SHUT DOWN OF SERVICE. CUSTOMERS MUST RECEIVE AT LEAST 48 HOURS NOTIFICATION PRIOR TO ANY SHUT DOWN. THE DISTRICT MUST RECEIVE NOTICE FROM THE CONTRACTOR OF THE SHUT DOWN AT LEAST 48 HOURS PRIOR TO CUSTOMER NOTIFICATION.

4. ALL DUCTILE IRON PIPE AND FITTINGS SHALL BE POLY-WRAPPED PER SPECIFICATIONS.

5. THE COST OF PROVIDING TEMPORARY WATER SERVICE TO THE BUILDINGS INDICATED ON THE PLAN SHALL BE AN INCIDENTAL COST FOR WHICH SEPARATE PAYMENT WILL NOT BE MADE. IF PROPERTIES REQUIRING A TEMPORARY WATER CONNECTION HAVE MALFUNCTIONING SILCOCKS OR NO EXTERIOR PLUMBING, IT MAY BE NECESSARY TO EXCAVATE AND CONNECT INTO THE EXISTING SERVICE LINE BEHIND THE EXISTING SHUT-OFF VALVE TO PROVIDE TEMPORARY SERVICE.

6. PROVIDE TEMPORARY MAIN CONNECTION TO HYDRANT USING LL BRASS OR 304 SS ADAPTER, 304 SS NPT TO HDPE TRANSITION, AND FLANGED HDPE PIPING TO BRING PIPING ELEVATION FROM HYDRANT PORT TO GRADE. PROVIDE PIPING SUPPORTS/BLOCKING AT FITTINGS. HDPE SHALL BE AWWA C906, SDR 11 WITH IPS FLANGE ADAPTERS AND DI BACKUP RINGS, DIMENSIONS PER AWWA C207. ALL PIPING AND FITTINGS SHALL BE NSF 61.

7. PROVIDE FLANGED LL DOUBLE CHECK VALVE BACKFLOW DEVICE, SAME NOMINAL SIZE AS TEMP MAIN, AT EACH HYDRANT CONNECTED TO A TEMPORARY MAIN. PROVIDE FLANGED RESILIENT SEATED GATE VALVES FOR ISOLATION, AND PROVIDE UPSTREAM AND DOWNSTREAM TAPS. REMOVE BACKFLOW ONLY UPON OWNER'S REQUEST AND PROVIDE FLANGED HDPE REPLACEMENT SPOOL PIECE. HDPE SHALL BE AWWA C906, SDR 11 WITH IPS FLANGE ADAPTERS AND DI BACKUP RINGS. FLANGE DIMENSIONS PER AWWA C207. ALL PIPING AND FITTINGS SHALL BE NSF 61. PROVIDE DOCUMENTATION OF ANNUAL INSPECTION BY A PERSON CERTIFIED BY THE NEW ENGLAND WATER WORKS ASSOCIATION OR AMERICAN BACKFLOW PREVENTION ASSOCIATION.

8. INSTALL 4" TEMPORARY FIRE DEPT CONNECTION (TYP.), 4" GATE VALVE, 90° ELBOW, RISER PIPE, 90° ELBOW, AND 4-1/2" NPT STEAMER PORT CONNECTION WITH CAP. ALL JOINTS TO BE RESTRAINED. STEAMER PORT, RISER AND TEE TO BE ANCHORED TO THE GROUND. OUTLET TO BE BETWEEN 1' AND 2' OFF THE GROUND.

9. REMOVE ALL OLD PIPING NOT EXPLICITLY CALLED OUT FOR ABANDONMENT.

10. TEMPORARY WATER SYSTEM SHALL ONLY BE ACTIVE BETWEEN APRIL 15TH AND OCTOBER 15TH. ALL WATER MAIN, EITHER EXISTING OR NEWLY INSTALLED, MUST BE ACTIVE BETWEEN OCTOBER 16TH AND APRIL 14TH. ALL 4" DIAMETER & LARGER TEMPORARY WATER LINES MUST BE BURIED WHEN CROSSING STREETS, DRIVEWAYS & SIDEWALKS.

11. CONTRACTOR MUST ALLOW OWNER SUFFICIENT TIME TO TRANSFER WATER SERVICES FROM EXISTING WATER MAIN TO TEMPORARY WATER SERVICES INSTALLED BY CONTRACTOR AND TO TRANSFER SERVICE TO NEW WATER MAIN/SERVICE LINE UPON SUCCESSFUL TESTING OF SAMPLE FOR ABSENCE OF BACTERIA. THE CONTRACTOR SHALL NOT CLAIM ANY DELAY-RELATED COSTS OR TIME RELATED TO THIS WORK.

12. REPLACE ALL SERVICES TO BE RENEWED FROM MAIN TO STREET LINE WITH 1" COPPER PIPING, UNLESS CALLED OUT TO BE REPLACED DIFFERENTLY.

13. SIDEWALKS MUST REMAIN OPEN AT ALL TIMES OR REASONABLE DETOURS PROVIDED.

14. LOCATIONS OF UTILITIES OTHER THAN WATER ARE APPROXIMATE, AND NOT ALL UTILITIES ARE SHOWN. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING, SUPPORTING AND PROTECTING ALL UTILITIES DURING INSTALLATION OF THE WATER MAIN.

15. TEMPORARY WATER (INCLUDING SERVICES) SHALL BE ACTIVE FOR PHASE I AS SHOWN ON THE DRAWINGS BEFORE EXISTING WATER MAIN IS TAKEN OUT OF SERVICE. NEW MAIN SHALL BE PRESSURE/LEAK TESTED, DISINFECTED AND HAVE A SUCCESSFUL TESTING SAMPLE FOR ABSENCE OF BACTERIA BEFORE PHASE II MAY COMMENCE. LAYOUT OF TEMPORARY WATER (INCLUDING SERVICES) FOR PHASE II CAN OCCUR CONCURRENTLY WITH PHASE I WATER MAIN REPLACEMENT WORK. A SIMILAR SCHEDULE IS REQUIRED FOR PHASE III.

16. THERE IS A CONCRETE SLAB UNDER THE PAVEMENT ON MAIN STREET. THE CONCRETE REMOVED WILL NOT BE REPLACED.

LEGEND

— EXISTING WATER MAIN

----- PROPOSED WATER MAIN

--- TEMPORARY WATER MAIN

- - - - - PROPOSED/RENEWED SERVICE

○ --- RECONNECT SERVICE

PROJECT:

330277

MAIN STREET

(NEW YORK TO MEMORY)

WATER MAIN REPLACEMENT

SOUTH PORTLAND, ME

DRAWN BY:
MAM

DESIGN BY:
WEP

CHECKED BY:
WEP

DATE:
02/23/2016

Portland Water District












ASSET MANAGEMENT AND PLANNING DEPARTMENT






225 DOUGLASS STREET, PORTLAND ME 04104

(207) 774-5961 • WWW.PWD.ORG




SHEET:

4 OF 6






NOTE: BELL
TYPE BASE
WITH BOTTOM LIP




(NUMBERS ARE FOR 5 1/4" BUFFALO VALVE BOXES)
(BASE SECTION MAY BE USED AS INTERMEDIATE SECTION)

VALVE BOX & COVER




NOTE: DIMENSIONS APPLICABLE FOR SIGMA COMPACT BENDS.
FOR TYLER COMPACT BENDS, ADD 1/2" TO "D" DIMENSION
AND SUBTRACT 1/2" FROM "L" DIMENSION. FOR OTHER
FITTINGS REFER TO MANUFACTURER'S RECOMMENDATIONS.



H	6" PIPE		8" PIPE		12" PIPE	
	D	L	D	L	D	L
12"	1' 6-1/2"	0' 10-1/2"	1' 7-1/2"	0' 9-1/2"	1' 11-1/2"	0' 5-1/2"
13"	1' 7-1/2"	0' 11-7/8"	1' 8-1/2"	0' 10-3/8"	2' 0-1/2"	0' 6-7/8"
14"	1' 8-1/2"	1' 1-5/16"	1' 9-1/2"	1' 0-5/16"	2' 1-1/2"	0' 8-5/16"
15"	1' 9-1/2"	1' 2-11/16"	1' 10-1/2"	1' 1-11/16"	2' 2-1/2"	0' 9-11/16"
16"	1' 10-1/2"	1' 4-1/8"	1' 11-1/2"	1' 3-1/8"	2' 3-1/2"	0' 11-1/8"
17"	1' 11-1/2"	1' 5-9/16"	2' 0-1/2"	1' 4-9/16"	2' 4-1/2"	1' 0-9/16"
18"	2' 0-1/2"	1' 6-15/16"	2' 1-1/2"	1' 5-15/16"	2' 5-1/2"	1' 1-15/16"
19"	2' 1-1/2"	1' 8-3/8"	2' 2-1/2"	1' 7-3/8"	2' 6-1/2"	1' 3-3/8"
20"	2' 2-1/2"	1' 9-13/16"	2' 3-1/2"	1' 8-13/16"	2' 7-1/2"	1' 4-13/16"
21"	2' 3-1/2"	1' 11-3/16"	2' 4-1/2"	1' 10-3/16"	2' 8-1/2"	1' 6-3/16"
22"	2' 4-1/2"	2' 0-5/8"	2' 5-1/2"	1' 11-5/8"	2' 9-1/2"	1' 7-5/8"
23"	2' 5-1/2"	2' 2"	2' 6-1/2"	2' 1"	2' 10-1/2"	1' 9"
24"	2' 6-1/2"	2' 3-7/16"	2' 7-1/2"	2' 2-7/16"	2' 11-1/2"	1' 10-7/16"
25"	2' 7-1/2"	2' 4-7/8"	2' 8-1/2"	2' 3-7/8"	3' 0-1/2"	1' 11-7/8"
26"	2' 8-1/2"	2' 6-1/4"	2' 9-1/2"	2' 5-1/4"	3' 1-1/2"	2' 1-1/4"
27"	2' 9-1/2"	2' 7-11/16"	2' 10-1/2"	2' 6-11/16"	3' 2-1/2"	2' 2-11/16"
28"	2' 10-1/2"	2' 9-1/8"	2' 11-1/2"	2' 8-1/8"	3' 3-1/2"	2' 4-1/8"
29"	2' 11-1/2"	2' 10-1/2"	3' 0-1/2"	2' 9-1/2"	3' 4-1/2"	2' 5-1/2"
30"	3' 0-1/2"	2' 11-15/16"	3' 1-1/2"	2' 10-15/16"	3' 5-1/2"	2' 6-15/16"
31"	3' 1-1/2"	3' 1-5/16"	3' 2-1/2"	3' 0-5/16"	3' 6-1/2"	2' 8-5/16"
32"	3' 2-1/2"	3' 2-3/4"	3' 3-1/2"	3' 1-3/4"	3' 7-1/2"	2' 9-3/4"
33"	3' 3-1/2"	3' 4-3/16"	3' 4-1/2"	3' 3-3/16"	3' 8-1/2"	2' 11-3/16"
34"	3' 4-1/2"	3' 5-9/16"	3' 5-1/2"	3' 4-9/16"	3' 9-1/2"	3' 0-9/16"
35"	3' 5-1/2"	3' 7"	3' 6-1/2"	3' 6"	3' 10-1/2"	3' 2"
36"	3' 6-1/2"	3' 8-7/16"	3' 7-1/2"	3' 7-7/16"	3' 11-1/2"	3' 3-7/16"
37"	3' 7-1/2"	3' 9-13/16"	3' 8-1/2"	3' 8-13/16"	4' 0-1/2"	3' 4-13/16"
38"	3' 8-1/2"	3' 11-1/4"	3' 9-1/2"	3' 10-1/4"	4' 1-1/2"	3' 5-1/4"
39"	3' 9-1/2"	4' 0-11/16"	3' 10-1/2"	3' 11-11/16"	4' 2-1/2"	3' 7-11/16"
40"	3' 10-1/2"	4' 2-1/16"	3' 11-1/2"	4' 1-1/16"	4' 3-1/2"	3' 9-1/16"
41"	3' 11-1/2"	4' 3-1/2"	4' 0-1/2"	4' 2-1/2"	4' 4-1/2"	3' 10-1/2"
42"	4' 0-1/2"	4' 4-7/8"	4' 1-1/2"	4' 3-7/8"	4' 5-1/2"	3' 11-7/8"
43"	4' 1-1/2"	4' 6-5/16"	4' 2-1/2"	4' 5-5/16"	4' 6-1/2"	4' 1-5/16"
44"	4' 2-1/2"	4' 7-3/4"	4' 3-1/2"	4' 6-3/4"	4' 7-1/2"	4' 2-3/4"
45"	4' 3-1/2"	4' 9-1/8"	4' 4-1/2"	4' 8-1/8"	4' 8-1/2"	4' 4-1/8"
46"	4' 4-1/2"	4' 10-9/16"	4' 5-1/2"	4' 9-9/16"	4' 9-1/2"	4' 5-9/16"
47"	4' 5-1/2"	4' 11-15/16"	4' 6-1/2"	4' 10-15/16"	4' 10-1/2"	4' 6-15/16"
48"	4' 6-1/2"	5' 1-3/8"	4' 7-1/2"	5' 0-3/8"	4' 11-1/2"	4' 8-3/8"
49"	4' 7-1/2"	5' 2-13/16"	4' 8-1/2"	5' 1-13/16"	5' 0-1/2"	4' 9-13/16"
50"	4' 8-1/2"	5' 4-3/16"	4' 9-1/2"	5' 3-3/16"	5' 1-1/2"	4' 11-3/16"
51"	4' 9-1/2"	5' 5-5/8"	4' 10-1/2"	5' 4-5/8"	5' 2-1/2"	5' 0-5/8"
52"	4' 10-1/2"	5' 7-1/16"	4' 11-1/2"	5' 6-1/16"	5' 3-1/2"	5' 2-1/16"
53"	4' 11-1/2"	5' 8-7/16"	5' 0-1/2"	5' 7-7/16"	5' 4-1/2"	5' 3-7/16"
54"	5' 0-1/2"	5' 9-7/8"	5' 1-1/2"	5' 8-7/8"	5' 5-1/2"	5' 4-7/8"
55"	5' 1-1/2"	5' 11-5/16"	5' 2-1/2"	5' 10-5/16"	5' 6-1/2"	5' 6-5/16"

TYPICAL MAIN OFFSET




TYPICAL METER PIT

5/8" TO 2" METERS

- METER BOX
- 1) TO BE INSTALLED AND SUPPLIED BY OWNER
 - 2) MINIMUM 4'-0" DIAMETER CONC. M.H. W/ CEMENT BASE
 - 3) WATER METER TO HAVE 5'-6" OF COVER AND IS TO BE SUPPLIED BY P.W.D.
 - 4) OWNER IS TO SUPPLY 2 VALVES INSIDE OF PIT (MINIMUM SEPARATION OF 2'-0")
 - 5) COPPER PIPE REQUIRED THRU METER PIT

- COVER PLATE
- 1) COVER MUST WEIGH LESS THAN 60 lbs.
 - 2) MINIMUM SIZE OF COVER WILL BE 28" DIAMETER.
 - 3) IF STEEL PLATE IS USED, TREAT WITH A COAT OF RUST INHIBITING PAINT.

- NOTES
- 1) THIS PIT IS TO BE PLACED ON PRIVATE PROPERTY NEAR THE STREET LINE.
 - 2) THIS TYPICAL PIT WAS NOT DESIGNED FOR ANY TRAFFIC LOAD
 - 3) THE PIT CAN BE ORDERED THRU OTHERS WITH SPECIAL DETAILS SUCH AS LARGER M.H. COVERS, ETC.
 - 4) THIS PIT WILL HOUSE UP TO TWO 5/8", 3/4", OR 1" METERS



TYP. HORIZONTAL METER SET