



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

Paul R. LePage  
GOVERNOR

David Bernhardt  
COMMISSIONER

August 05, 2016  
Subject: Intersection Improvements  
State WIN: 020207.00  
Location: **Mechanic Falls & Poland  
Amendment No. 2**

Dear Sir/Ms:

Make the following changes to the Bid Documents:

Add the attached "Special Provision Section 203 Excavation and Embankment" one page, dated June 27, 2016 to the bid documents.

On "Special Provision Section 643 Traffic Signals", page 74, first section titled "Add to Section 643.01 Description" **CHANGE** the first sentence from "This work shall consist of the installation of Advance Vehicle Detection on both Route 26 approaches via Wavetronix equipment." to **Now Read** "This work shall consist of the installation of Advance Vehicle Detection on both Route 26 approaches via Wavetronix equipment **or approved equal.**" Make this change in pen and ink.

On Plan Sheet 22 of 56, under the "Notes" **CHANGE** Note # 17 from "Advance detection for Route 26 approaches shall be Wavetronix Smart Sensor Advance with safe arrival technology and be aimed 260 feet from the stop bar no substitution will be allowed" to **Now Read** "Advance detection for Route 26 approaches shall be Wavetronix Smart Sensor Advance with safe arrival technology **or approved equal** and be aimed 260 feet from the stop bar." Make this change in pen and ink.

The following question has been received:

**Question:** On Sheet 11 of the plans there are two structures shown to be removed by others but for the foundation removal it says to see Special Provision 203.21 "Rock Excavation" but that Special Provision is not in the proposal book. Please clarify how the foundation removal is to be paid for.

**Response:** Please see "Special Provision Section 203 Excavation and Embankment", included in this amendment.

**Question:** The traffic signal note #17 on the plan sheet 22 specifies that only one brand of advance microwave detection can be furnished with "no substitutions allowed". Can an "or equal" be supplied for this item?

**Response:** Please see above changes to note 17 in the plans as addressed in this amendment.



PRINTED ON RECYCLED PAPER

**Question:** Would the Department consider extending the bid date by 1 week?

**Response:** No, the Department will not be extending the bid opening date for this project.

Consider this change and information prior to submitting your bid on **August 10, 2016**.

Sincerely,

A handwritten signature in black ink, appearing to read "George M. A. Macdougall". The signature is fluid and cursive, with the last name "Macdougall" being more prominent and written in a larger, bolder script.

George M. A. Macdougall P.E.  
Contracts & Specifications Engineer

SPECIAL PROVISION  
SECTION 203  
EXCAVATION AND EMBANKMENT

**Section 203 – Excavation and Embankment is amended as follows:**

Add to Section 203.01 Description:

This work shall consist of removing and disposing of concrete foundation and regrading of the remaining ground area, as required by the plans or as directed by the Resident.

Add to Section 203.07 Method of Measurement:

Removing concrete foundation will be measured for payment by the cubic yard of material removed.

Add to Section 202.08 Basis of Payment:

Removing and disposing of concrete foundations will be paid for at the contract unit price, which will be full compensation for removing and disposing and regrading.

Add to Pay Items

203.21 Rock Excavation

Pay Unit

Cubic Yard