



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

June 28, 2016
Subject: Office Drainage & Water
Service
State WIN: 021162.16S
Location: **Scarborough**
Amendment No. 2

Dear Sir/Ms:

Make the following change to the Bid Documents:

On page 38, "SPECIAL PROVISION, SECTION 910, (Special Work)", **ADD** the following after the fourth paragraph which begins with, "The Contractor shall remove and replace the water service...".

"The Contractor shall install a Reduced Pressure Zone Back Flow Preventer and coordinate with the Portland Water District for the water meter re-installation and RPZ testing.

The following questions were received at the mandatory pre-bid meeting and site walk through held June 23, 2016. Also attached is the pre-bid sign in sheet for your information.

Question: Who is responsible for removing and disposing of shrubs?

Response: It is the responsibility of the contractor.

Question: Does concrete slab at the main entrance stay or be replaced?

Response: The concrete slab shall be removed and replaced with 12" of aggregate subbase course-gravel and 2" hot mix asphalt pavement.

Question: Will cracks in the foundation be sealed from inside the basement also?

Response: NO, only the outside foundation will be sealed.

Question: Who will be responsible for ON-SITE traffic control?

Response: MaineDOT will be responsible for onsite traffic control. The contractor WILL be responsible for any and all traffic control on or near Pleasant Hill Rd.



PRINTED ON RECYCLED PAPER

Question: Does the concrete slab at the rear entrance contain a frost wall?

Response: This is not known. Drainage shall be placed as close to the slab as possible without jeopardizing the integrity of the slab.

Question: Who is responsible for loam and seed?

Response: Maine DOT will do the final loam and seed.

The following additional questions have been received:

Question: Could you please give us more information on the water proofing membrane you want? All the listed companys list many different products. If you want as specific product will you please give us a product number you approve.

Response: The product must meet ASTM C386 Standard Specification for high solid content, cold liquid- applied elastomeric Waterproofing Membrane. Brands that provide a product that achieve this include, but are not limited to, Sonoshield, TREMproof, or Protesheild.

Question: Could 2" plastic water line be used instead of 2" copper for cost saving measures?

Response: Yes, 2" CTS Plastic will be an approved alternative to copper.

Consider this change and information prior to submitting your bid on **July 6, 2016**.

Sincerely,

A handwritten signature in black ink, appearing to read "G. M. A. Macdougall". The signature is stylized and cursive.

George M. A. Macdougall P.E.
Contracts & Specifications Engineer



MaineDOT

Town SCARBOROUGH

WIN 021162.16S

Name (Please Print)	Representing
John Doe	Company Inc.
GARY PELLETIER	M.D.O.T.
Lindsay Dearborn	Dearborn Bros. Const.
Mitch Elliott	Shaw Brothers
Brian Shaw	Shaw Earthworks Inc
James Exley	DDI
MATT RAGUE	NEW ENGLAND EARTHWORKS INC.
ANDREW WARD	PRATT + SONS
PAUL PARIS	CUPP EXCAVATION
James Schneider	R.J. Gaudin
Travis Mopie	M.D.O.T.
Kyle Hall	MaineDOT