



Paul R. LePage
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

David Bernhardt
COMMISSIONER

February 29, 2016
Subject: Mill/Fill
State WIN: 021654.00, 021655.00 &
021656.00
Location: **Bangor & Brewer**
Amendment No. 1

Dear Sir/Ms:

The following questions have been received:

Question: In reference to item 502.26 Structural Concrete Roadway and Sidewalk Slabs can you define the limits of this work? Please define the depth, width and length of this repair.

Response: All sidewalk repair will be on the west side of the bridge downstream sidewalk repair 1 foot wide the width of the sidewalk down 3 inches when finished pave transition on the abutment.

Upstream sidewalk repair 1 foot wide the width of the sidewalk down 3 inches on the abutment when finished pave transition on the superstructure side 2 feet wide 6 foot width down 2 inches remove steel cover plate

Question: If detours are utilized, will work be allowed from 7:00AM to 7:00PM? Special Provision 105 and the detour plans state no work will be allowed between 7:00AM and 7:00PM.

Response: No work will be allowed from 7AM to 7PM. If a detour is utilized, a complete closure will be allowed from 7PM to 7AM. Otherwise, traffic flow must be provided as indicated.

Consider this information prior to submitting your bid on **March 2, 2016**.

Sincerely,

George M. A. Macdougall P.E.
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER