



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

August 18, 2016
Subject: Cotton Mill Bridge
Rehabilitation
State WIN: 022518.00
Location: **Yarmouth**
Amendment No.1

Dear Sir/Ms:

The following question has been received:

Question: What is the size & spacing of the reinforcing steel required in the bridge joint modification Type 3A & 3B shown on drawing 8, is the reinforcing steel to be uncoated or epoxy coated ?

Response: For bridge joint modification Types 3A & 3B shown on Sheet 8, the reinforcing steel shall be uncoated bars, shall match Standard Detail 520, and shall replace the existing reinforcement as shown in the as-built drawings. Transverse bars shall be #5 in size and equally spaced as shown on Sheet 8. Longitudinal bars shall be #4 in size and spaced at 8 inches across the deck.

Consider this information prior to submitting your bid on **August 24, 2016**.

Sincerely,

A handwritten signature in black ink that reads "George M. A. Macdougall".

George M. A. Macdougall P.E.
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER