STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

March 15, 2016
Subject: Milling/Overlay with
Drainage & Safety Improvements
State WIN: 022552.00
Location: **Woolwich**
Amendment No. 1

Dear Sir/Ms:

Make the following change to the Bid Documents:

REMOVE, pages 17 thru 20 "Proposal Schedule of Items", dated 02/26/2016 and **REPLACE** with the attached revised "Proposal Schedule of Items" 4 pages dated 03/09/2016.

The following question has been received:

Question: Item 606.362 Adjust guardrail, does the guardrail have wood or steel post?

Response: The guardrail posts are steel.

Consider this change and information prior to submitting your bid on **March 23, 2016**.

Sincerely,

George M. A. Macdougall P.E.
Contracts & Specifications Engineer

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022552.00 **Project(s):** 022552.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: **Alt Mbr ID:**

Contractor: _____

Proposal Line Number	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0010	202.202 REMOVING PAVEMENT SURFACE	57,015.000 SY				
0020	202.203 PAVEMENT BUTT JOINTS	660.000 SY				
0030	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	21.000 T				
0040	403.21041 HMA 9.5 MM – POLYMER MODIFIED THIN LIFT SURFACE TREATMENT	4,450.000 T				
0050	403.211 HOT MIX ASPHALT (SHIMMING)	1,000.000 T				
0060	403.213 HOT MIX ASPHALT 12.5 MM BASE	3,878.000 T				
0070	409.15 BITUMINOUS TACK COAT - APPLIED	6,818.000 G				
0080	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	50.000 CY				
0090	603.55 CONCRETE PIPE TIES	38.000 GP				
0100	603.7418 REMOVE & RELAY 18 INCH CONCRETE PIPE	160.000 LF				
0110	603.7424 REMOVE & RELAY 24 INCH CONCRETE PIPE	120.000 LF				
0120	603.743 REMOVE & RELAY 30 INCH CONCRETE PIPE	16.000 LF				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022552.00 **Project(s):** 022552.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: **Alt Mbr ID:**

Contractor: _____

Proposal Line Number	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0130	606.178 GUARDRAIL BEAM	50.000 LF				
0140	606.20 GUARDRAIL TYPE 3A - OVER 15 FOOT RADIUS	37.500 LF				
0150	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	68.000 EA				
0160	606.356 UNDERDRAIN DELINEATOR POST	2.000 EA				
0170	606.362 GUARDRAIL ADJUSTED	4,400.000 LF				
0180	613.319 EROSION CONTROL BLANKET	9,385.000 SY				
0190	618.14 SEEDING METHOD NUMBER 2	460.000 UN				
0200	619.12 MULCH	460.000 UN				
0210	627.407 REFLECTORIZED PLASTIC WHITE OR YELLOW PAVEMENT MARKING	32.000 SF				
0220	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	220,000.000 LF				
0230	629.05 HAND LABOR, STRAIGHT TIME	50.000 HR				
0240	631.111 TRACTOR MOUNTED HYDRAULIC HAMMER	20.000 HR				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022552.00 **Project(s):** 022552.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: **Alt Mbr ID:**

Contractor: _____

Proposal Line Number	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0250	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	350.000 HR				
0260	631.133 SKID STEER (INCLUDING OPERATOR)	30.000 HR				
0270	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	700.000 HR				
0280	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR				
0290	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	60.000 HR				
0300	639.19 FIELD OFFICE TYPE B	1.000 EA				
0310	652.33 DRUM	60.000 EA				
0320	652.34 CONE	150.000 EA				
0330	652.35 CONSTRUCTION SIGNS	852.000 SF				
0340	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	140.000 CD				
0350	652.38 FLAGGER	2,750.000 HR				
0360	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022552.00 **Project(s):** 022552.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: **Alt Mbr ID:**

Contractor: _____

Proposal Line Number	Item ID / Description	Approximate Quantity and Units	Unit Price Dollars	Unit Price Cents	Bid Amount Dollars	Bid Amount Cents
0370	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	____
0380	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	____
	Section: 1		**Total:**		_____	____
			Total Bid:		_____	____